

COMBUSTION

DEVOTED TO THE ADVANCEMENT OF STEAM PLANT DESIGN AND OPERATION

June, 1944

JUL 7 1944



Assembling C-E Boiler for Power Train

**Inertia Effect of Variable-Speed Control
of Induced-Draft Fan Wheels ►**

**High-Pressure and High-Temperature
Steam for Marine Use ►**



Convoys get through these days. Get through for the most part without loss or damage to a single ship. The effect of that achievement on our Axis enemies can scarcely be over estimated.

No small part of the credit for this result is due our new escort carriers — the Baby Flat Tops — shown above. These vital combat ships, known as the Casablanca Class, are built at the Vancouver Yard of the Kaiser Shipbuilding Co.

To do the job which has been assigned to them, these ships must be fast, maneuverable and dependable. These attributes

originate in the engine room—start with the boilers that supply the steam, and deep in the hulls of many of these "sub busters" are C-E Boilers. Boilers built to do their job reliably and efficiently by men who have the skill, the facilities and the determination to accomplish that result.

The same skill and facilities which are now producing this reliable steam generating equipment for purposes of war will be ready to serve you afterwards by providing an installation that is ideally suited to your particular steam generation needs, whether at sea or on land.

A-780

COMBUSTION ENGINEERING

200 MADISON AVENUE

NEW YORK 16, N. Y.

Canadian Associates: COMBUSTION ENGINEERING CORPORATION LIMITED, Montreal, Toronto, Winnipeg, Vancouver

COMBUSTION

DEVOTED TO THE ADVANCEMENT OF STEAM PLANT DESIGN AND OPERATION

VOLUME FIFTEEN

NUMBER TWELVE

CONTENTS

FOR JUNE 1944

FEATURE ARTICLES

- Inertia Effect of Variable-Speed Control of Induced-Draft Fan Wheels..... *by Murray S. Kice*..... 38
- Power Trains to Serve Military Needs in Devastated Regions Abroad..... 41
- Necessity for Research on Combustion Rates and Ash Behavior..... *by A. R. Mumford*..... 43
- High-Pressure and High-Temperature Steam for Marine Use..... *by W. H. Armacost*..... 48
- Industrial Power Requirements..... 52

EDITORIALS

- Semi-Outdoor Plants..... 37
- Extra Home-Front Tasks..... 37
- Power Trains..... 37

DEPARTMENTS

- New Catalogs and Bulletins..... 56
- Advertisers in This Issue..... 60
- General and Classified Index, Volume Fifteen, July 1943 through June 1944..... 57

H. STUART ACHESON,
Advertising Manager

ALFRED D. BLAKE,
Editor

THOMAS E. HANLEY,
Circulation Manager

Published monthly by COMBUSTION PUBLISHING COMPANY, INC., 200 Madison Avenue, New York
A SUBSIDIARY OF COMBUSTION ENGINEERING COMPANY, INC.

Frederic A. Schaff, President; Charles McDonough, Vice-President; H. H. Berry, Secretary and Treasurer.

COMBUSTION is sent gratis to engineers in charge of steam plants from 500 rated boiler horsepower up and to consulting and designing engineers in this field. To others the subscription rate, including postage, is \$2 in the United States, \$2.50 in Canada and Great Britain and \$3 in other countries. Single copies: 25 cents. Copyright, 1944 by Combustion Publishing Company, Inc. Issued the middle of the month of publication.

Publication office, 200 Madison Ave., New York **CCA** Member of the Controlled Circulation Audit, Inc.

Printed in U. S. A.

Score:
11 Boilers
11 Flowmatics

5-1942


Gentlemen:
 Regarding the operation of Copes **FLOWMATIC REGULATORS** this advises
 we are obtaining satisfactory results.

Remarks: **We ordered three more Copes Flowmatic
 Regulators. Score - 11 Boilers - 11 Copes Flowmatic
 Regulators.**

Wyman-Gordon Co.
 By **Max R. Boye**
 Chief Engineer
 Power Plant

IN 1941, the Wyman-Gordon Company, Ingalls-Shepard Division, Harvey, Ill., installed their first Flowmatic Regulator. Confronted with the problem of maintaining close boiler water level control in spite of severe load fluctuations produced by forging operations, they found Flowmatic to be the correct solution. As Mr. Max R. Boye, Chief Engineer of the Power Plant, has remarked on the return card of our routine check-up, the score is now 11 Boilers, 11 Copes Flowmatic Regulators.

Proved performance of this kind accounts for the remarkable record of more than 825 Copes Flowmatic installations since its introduction only 5 years ago.



The Copes Flowmatic Regulator offers a simple reliable means of maintaining exacting feed water control geared to the requirements of modern boiler design. It is especially valuable on installations subject to severe load fluctuations. For details, write for Bulletin 429-A.

**OVER
 60,000
 COPS
 FEED WATER
 REGULATORS
 IN SERVICE**

NORTHERN EQUIPMENT COMPANY • 646 Grove Drive, Erie, Pa.
 Feed Water Regulators • Pump Governors • Differential Valves • Liquid Level Controls • Reducing Valves and Desuperheaters
 BRANCH PLANTS IN CANADA, ENGLAND • REPRESENTATIVES EVERYWHERE

★ **GET CLOSER LEVEL CONTROL WITH THE FLOWMATIC**
 ★ **REGULATOR**

EDITORIAL

Semi-Outdoor Plants

Indications point to continuance of high construction costs during the post-war period; perhaps not at the present level but assuredly above that of pre-war days, as there is little likelihood of wage scales reverting to former levels. This leads to some speculation as to how it may influence power plant design of the future, particularly building structures. Will it presage more semi-outdoor plants?

Plants of this type have long ceased to be a novelty. Many have been in service for the last ten or twelve years in varied climates and in both the central station and industrial power fields. The number is much larger than one would assume without an actual count and they appear to have been satisfactory in all respects. In general, such construction has been confined to medium-size installations. In most cases the turbine-generators have been housed and the boiler plant exposed, and in a few the reverse procedure has been adopted, with protection to the operating galleries.

Compared with the conventional fully housed plant, very substantial savings in building materials and labor are reported, and there is likely to be a reduction in maintenance. Operating economy is not affected.

It is not probable that such simplified construction will find application to large installations in metropolitan areas where the differential between the two types forms a proportionately smaller part of the total installation cost and where traditional conservatism is likely to favor the conventional design. However, within the already proved range, post-war economic conditions would appear to favor wider adoption of such plants.

Extra Home-Front Tasks

Everybody has heard of the "Dollar a Year Men" at Washington—leaders in industry who are contributing their time and experience to furthering various phases of the war effort. But their number is infinitesimal compared with the many thousands of business men and engineers throughout the country who are freely giving their time to innumerable war activities. Upon them depends most of the organization work for bond drives, Red Cross and similar campaigns, but in addition to these widespread projects in which the general public participates, there are innumerable other campaigns calling for their specialized knowledge, such as re-employment studies, post-war planning, national publicity to conserve paper and other strategic materials, production clinics and the recently inaugurated Fuel Conservation Program. The last mentioned alone will require the active participation of several thousand engineers and valuable assistance has already been rendered by several trade associations in the preparation of forms and helpful information.

Full credit is due these individuals who have taken on such home-front duties, often in addition to their regular work because of manpower shortage or when it cannot be delegated to others. But aside from this, the companies that employ them are to be highly commended not only for their financial support but for their unstinted cooperation in making available the services of executives and other key men. This has been especially true of the larger corporations.

If it were possible to evaluate in dollars the time thus gratuitously contributed, the total would represent a staggering sum. Unfortunately, little of this is known to the general public. If it were, the business world would be better fortified against the attacks of malcontents and politicians.

Power Trains

Very little has appeared in print concerning the destruction of power plants in battle areas as well as by bombing far within enemy territory. That such destruction must be considerable is conceivable from the fact that power plants are one of the primary objects of attack as a means of crippling enemy production and hampering military efforts. Moreover, they have usually been objects of systematic demolition by retreating forces in order to impede the re-establishment of civilian life in captured cities and towns. In some cases, the destruction is reported to have been so extensive as to preclude restoration of service; in others it has been such as to require weeks for repairs. Months would be required to erect new power equipment. Meanwhile, lack of electricity supply to serve the most essential civilian and military needs constitutes a serious handicap.

It was in anticipation of such situations that the Allied Governments some time ago wisely undertook the planning of a large number of mobile steam power plants, mounted on railway cars, that could be readily shifted to localities where most needed. Of these a considerable number are now nearing completion in the United States, and have received more or less publicity in the daily press under the designation "Power Trains." These are built in sizes of 5000, 3000 and 1000 kilowatts in order to provide flexibility in meeting individual local requirements.

Because of the wide range in localities where they are likely to be employed, many unique problems in design were involved. These include the meeting of limitations imposed by railway clearances in various countries, axle loading, the possibility of having to burn very low grade coals, ability to operate in either torrid or frigid zones and scarcity of water supply.

These Power Trains have already been discussed informally at several engineering society meetings, one of which is briefly reported in this tissue. It is expected that COMBUSTION will be privileged to give further details in a forthcoming issue.

Inertia Effect of Variable-Speed Control of Induced-Draft Fan Wheels

By Murray S. Kice, Ch. Engr.

American Blower Corporation, Detroit

SIMPLE algebraic equations can be employed to calculate deceleration of the rotating parts of an induced-draft fan as soon as the driving power has been shut off, with the fan, however, continuing to operate in its regular system. The flywheel effect of the rotating parts is braked by the air delivery and wheel torque, plus journal friction. The braking effect of the journal friction is relatively insignificant until the wheel speed becomes very low. The tabulation shows the relation between the fan brake horsepower, and the journal friction horsepower. Wheel windage is included in the fan brake horsepower. Journal friction tends to produce a constant torque, whereas the fan horsepower torque and windage vary as the square of the fan revolutions per minute.

The tabulated WR^2 of the three typical induced-draft fans as made by the writer's company, includes the wheel, and its shaft. The WR^2 of a suitable hydraulic coupling runner is included merely to represent an average value for the rotating part of a variable-speed drive. The ratio of this to the WR^2 of the whole is very low, hence any nominal difference in the inertia effect of various variable-speed-drive rotors, should not affect the final results significantly. The data plotted here for deceleration do not account for any energizing from the drive during deceleration, as this is a study only of the effect of flywheel energy against the running output torque of the rotating parts of these induced-draft fans.

Acceleration-time curves are not plotted because here time is a function of the driver torque acceleration versus rotational WR^2 , plus the square increase in torque, due to fan air delivery. The result is a matter of initial torque provision. Since this concerns the case of an induced-draft fan, the gas density and the system characteristic have to be assumed to remain unchanged during the period of deceleration. A change in gas temperature, for example, will change slightly the fan-wheel torque. On deceleration, the gas temperature is likely to decrease which increases the density of the gas, which, in turn, would slightly increase deceleration. The inertia effect of decreasing gas flow, likewise is ignored.

The approach to this method of calculation is to consider the mass of the rotor at rest, and to calculate its acceleration to full speed when a constant torque is applied. This is equal to the driving torque of the fan at full speed. Hence, with the above assumptions, if this

This study is to illustrate that the use of straight variable-speed mechanical-draft fan drive is no deterrent to practical rapid boiler load swings. Variable-speed drive affords considerable power and maintenance savings, compared to constant-speed drive, and the latter requires, also, time to operate its capacity control devices.

constant torque, which is equal in value to the fan full-speed torque, is applied to brake the mass of the rotor, it is assumed the same time would elapse. In other words, acceleration time would equal deceleration time. The tabulation shows the time in seconds, required for the mass of three different induced-draft fan rotors, all selected and designed for the common duty shown.

The actual fan, however, would not behave in this manner because, as it decelerates, the air-brake torque falls off as the square of the revolutions per minute. There is an increasing gain of flywheel effect to continue rotation, against the air brake effect to slow down the fan wheel. With the above assumptions, theoretically the fan never would come to complete rest (with no journal friction) as there always would remain slightly more flywheel effect than air brake torque, at infinitesimal rpm. The calculation of such a function is a task employing calculus. This, however, can be approximated by setting up the equation, then calculating decrements, of say 10 rpm, from full speed down to a practical low speed limit. The derivation of the formulas is as follows:

Derived from $F = MA$, we have, for a rotating body;

$$T = IA \quad (1)$$

where

T = torque, in foot-pounds
 I = moment of inertia
 A = angular acceleration

$$I = \frac{WR^2}{32.2} \quad (2)$$

where

W = weight, in pounds
 R = radius of gyration, in feet
32.2 = acceleration due to gravity, ft/sec/sec

$$A = \frac{w}{t} = \frac{2\pi N}{60t} \quad (3)$$

where

π = 3.1410
 w = radians per second
 t = time, in seconds
 N = revolutions per minute

Substituting in (1), equations (2) and (3), we have

$$T = \frac{WR^2}{32.2} \times \frac{2Pi N}{60t} = \frac{WR^2 N}{307.6t} \quad (4)$$

Transposing equation (4), provides the equation for seconds time for deceleration, namely,

$$t = \frac{WR^2 N}{307.6T} \quad (5)$$

This equation calculates the time for constant torque and produces the seconds time shown in the tabulation.

Since the fan-braking torque varies as the square of the fan rpm, and since it is desired to calculate 10 rpm decrements, equation (5) becomes

$$t = \frac{WR^2 dN}{307.6T(Ni/No)^2} \quad (6)$$

where

$dN = 10$ rpm

$Ni =$ average rpm of decrement

$No =$ full fan speed, rpm


Thus for each wheel the tabulation provides values for all factors in equation (6) except Ni and t . Therefore, these



Radial-tip rotor

Each decremental time is added accumulatively to obtain the time intervals for 50 rpm. These values together with the corrected percent rpm are used to plot the curves to show the relation of the deceleration of these three types of wheels. They should agree with field observations except for minor errors caused by stack draft and internal hydraulic coupling windage to maintain rotation, versus journal friction to reduce rotation. These balance out in the case of the hydraulic-coupling drive to produce a minimum empty coupling fan speed of from 10 to 20 per cent of top fan speed, depending upon the amount of stack draft and the friction of the bearings.

A study of the family of curves illustrates another advantage of the forward-curve fan for induced-draft service, when variable-speed operation is employed. It possesses powerful "air brake" for deceleration in the upper half power range of the boiler. This has been known from experience for a number of years, but proba-



Radial-blade rotor

values become constants that can be substituted in equation (6) to form three equations, one for each of the three induced-draft fan wheels.

72 $\frac{5}{8}$ -in. wheel diameter,

forward curve $t = \frac{0.0952}{(Ni/710)^2} \quad (7)$

87-in. wheel diameter,

radial tip $t = \frac{0.2132}{(Ni/890)^2} \quad (8)$


142-in. wheel diameter,

radial blade $t = \frac{0.667}{(Ni/505)^2} \quad (9)$

where

$t =$ seconds for 10 rpm deceleration of these three specific forward-curve, radial-tip and radial-blade fan wheels, respectively, together with their shaft and proper size hydraulic coupling runner mounted on the fan shaft

$Ni =$ average rpm in the decrement, which is taken other than the arithmetic average, to compensate closer for the slope of the curve



Forward-curve type

bly this is the first time such a direct comparison has been calculated and plotted. It represents the duty and size of one of two Sirocco induced-draft fans that have operated at top load continuously during the past year and

COMPARISON OF THREE INDUCED-DRAFT FANS

	Duty.....285,000 cfm		
	S.P.....19 1/4 in.		
	Temperature.....350 F		
	1/2 outlet velocity pressure recovered		
Type	Forward Curve	Radial Tip	Radial Blade
Wheel diam., in.	72 5/8 (1 DW)	87	142
Rpm	710	890	505
Bhp	1,218	1,300	1,260
WR ² , lb (ft) ²			
Wheel	24,570	48,500	265,000
Hydraulic coupling runner	1,450	930	2,950
Shaft	330	900	955
Total WR ²	26,350	50,330	268,905
Full-speed torque, ft-lb	9,000	7,670	13,100
Journal friction H _p at full speed	1.5	3.1	2.9
WR ² time to accelerate from rest to full speed, based on torque of full speed horsepower, sec	6.8	19.0	33.6


a half. The low WR^2 of this fan arises mainly from its lesser diameter, from which radius is squared; also this low WR^2 favors rapid acceleration from low speed. It is hastened by over-increasing the torque of the variable-

speed transmission, meaning that the top speed full torque of the driving motor could become available to accelerate the fan wheel if it ever becomes necessary to make such a provision in the initial design of the equipment. This is available, of course, for any type of wheel, but the wheel's acceleration effect is greater for the low WR^2 rotating parts.

On the decelerating phase, the forward-curve fan requires only 28 sec to come down from top speed to 20 per cent, which is approximately 20 per cent boiler capacity. The radial tip fan requires 75 sec; or in 28 sec, it would reduce to 40 per cent speed. The radial blade fan requires 137 sec to reduce to 20 per cent speed; or in 28 sec, it would reduce to only 55 per cent speed.

There is a question as to what is the lowest boiler rating below which there is no value to rapid deceleration. This depends upon circumstances, but a good average probably lies between 20 per cent and 30 per cent boiler load.

Another question arises at top boiler load. If an automatic control system is adjusted to the very rapid boiler rating change cycle here illustrated, the question may be whether the boiler and its auxiliaries can take these quick changes without hunting.



Deceleration time of induced-draft fan rotors—flywheel energy vs gas braking torque with journal and minor factors neglected

Power Trains to Serve Military Needs in Devastated Regions Abroad

These brief notes on the 5000-kw and 1000-kw power trains were released through a recent meeting of the Metropolitan Section A.S.M.E. Further details and illustrations of the larger units will appear in the July issue.

A LARGE number of portable power plants on wheels, or so-called "power trains," in capacities of 1000, 3000 and 5000 kw, are now under construction in the United States for use of the armed forces of the United Nations or for restoring electric service in devastated reconquered areas. They will serve to make power available quickly anywhere that railroad tracks exist or can be laid. It is anticipated that they will find use in western Russia, North Africa, Italy and possibly China or any other localities as military operations advance; perhaps in central or western Europe. The large number under construction was dictated by these varied needs.

In such areas where electric power plants have been destroyed or put out of commission, power will be required by the occupying military authorities for hospitals, machine shops, repair shops, water supply and sewage systems and as replacement plants for certain other services. Mobile power plant capacity of ten per cent or less of that previously existing in a given area before devastation has been estimated as sufficient to meet such emergency demands.

Many special problems were involved in designing these power trains, such as ability to burn any kind of coal that may be available, particularly the poorer grades found in certain parts of Europe; complete independence of condensing water supply; ability to operate in sub-zero or torrid temperatures; and, in the case of the larger units, limitations of weight imposed by permissible axle loadings which abroad are less than in this country; and, finally, width and height of track clearances, here and abroad.

These power trains were the subject of a meeting of the Metropolitan Section, A.S.M.E. (New York) on May 17 at which the three speakers, as representatives of the principal companies supplying the power equipment for the 5000-kw and the 1000-kw units, discussed their respective phases of the work. They were C. M. Laffoon of Westinghouse Electric & Mfg. Company, who described the project in general and dealt with the electric generating features; Otto de Lorenzi of Combustion Engineering Company, who discussed the steam-generating units and firing equipment for the 5000-kw trains; and F. G. Ely of Babcock & Wilcox Company who dealt with the boilers for the 1000-kw trains.

Mr. Laffoon stated that his company is now building forty-five of the 1000-kw and ten of the 5000-kw trains. These are assembled in specially designed railway cars, with suitable trucks for transportation over railroads

to points of shipment and for location on railway sidings, where needed, at which points they will be provided with supplementary foundation supports. The 5000-kw train consists of eight cars, namely, two for the steam-generating units, one for water, two for the air-cooled condensers and fans, one for the turbine-generator with its electrical equipment, one for auxiliaries and one for the crew. The 1000-kw train consists of three cars.

Under present war emergency conditions, Mr. Laffoon explained, the primary objective in designing and building electric-generating plants of this type, is to obtain the maximum output per unit of materials to meet actual operating conditions. The specification requirement that the generating plant be capable of being transported over railroads in a completely assembled condition necessitated that the cars be arranged in tandem and that the design be restricted, as previously mentioned, by height and width limitations, weight per axle, space in the cars and limited water supply for makeup and cooling. Hence, air-cooled surface condensers are employed to keep makeup to a minimum on the 5000-kw units and a conventional surface-type condenser is used in conjunction with a cooling tower on the 1000-kw units.

Stacks and ash hoppers will be detached during transit and set up when a train has reached its destination.

Several of the 5000-kw trains are already assembled and tests will shortly be completed.

Steam Generating Units


In describing the two steam-generating units for each of the 5000-kw trains, Mr. de Lorenzi stated that these are of the C-E two-drum, water-tube type, with water-cooled furnace, drainable superheater and Elesco fin-tube economizer, forced- and induced-draft fans; the complete unit being specially designed for low head room and in accordance with the other limitations mentioned. Each of the two units is rated at 40,000 lb of steam per hour at 625 psi and 750 F total steam temperature at the superheater outlet. Drum design pressure is 660 psi. The fully water-cooled furnace is an adaptation of locomotive design, employing a rear arch and is fired by a Standard spreader stoker of the type commonly employed in locomotive practice. The same applied to the grates which are of the Hulson type. Rated output was calculated on low-grade coal of approximately 7300 Btu per lb heating value and an ash-softening temperature of approximately 1800 F.

Mr. Ely stated that each 1000-kw train has one 16,000-lb per hr B & W integral furnace type of boiler, of the two-drum bent-tube type with four-pass superheater, designed to operate at 420 psi and 725 F total steam temperature. It is fired by a Standard stoker serving a Hulson tuyère-type grate, such as is commonly used in locomotive practice.

Simplicity OF OPERATION

It's easy to keep your EYE-HYEs working reliably while our new production goes mainly to ships

EYE-HYE Remote Reading Water Level Indicator



YOURS may be one of the boiler rooms fortunately equipped with Reliance remote-reading EYE-HYE Gages. Their convenience, economy, safety and extremely simple maintenance is appreciated by even the newer operators who have had no previous contact with this device.

To get used to the eye-high convenience and sharp, easily readable water level indication of EYE-HYE instead of the high-perched conventional water gage is a matter of minutes. To understand its principle of operation takes no long period of study.

EYE-HYE embodies the design and action of a "U" tube manometer. The visible green indicating fluid is raised

or lowered by a difference in hydrostatic head pressure generated by rising or lowering of water in the boiler. No deviation from accurate water level indication can occur, after correct installation. After a period of time it may be necessary to blow down to eliminate sedimentation in tubes and valves—a simple operation.

It's interesting to wide-awake engineers to know the "workings" of the devices and controls they have to deal with. By means of the diagram reproduced here, Reliance Bulletin 382-C explains EYE-HYE in detail. Reliance Instruction Manual No. 440 not only covers installation procedure but gives full instructions for maintenance.



At left, the Unitemp, which maintains an even temperature in both hydrostatic legs, thus assuring accuracy of the EYE-HYE under all conditions. . . At right, one model of the EYE-HYE.



The Reliance Gauge Column Co., 5902 Carnegie Ave., Cleveland 3, O.

60
Years of
Boiler
Protection

BOILER SAFETY DEVICES since 1884
Reliance

Necessity for Research on Combustion Rates and Ash Behavior*

By A. R. MUMFORD

Development Engineer, Combustion Engineering Company, Inc.

As timely problems in the field of fuel research, the author suggests (1) studies of the relation between hot-spot and average furnace heat releases to the end that higher combustion rates or less furnace volume may be possible, and (2) further studies on the behavior of ash to ameliorate present troubles. As a means of obtaining such information, the development of special means for measuring local conditions are advocated.

THE field of research in fuels is so large that it will be impossible, within the scope of this paper, to more than mention some of the problems concerned with higher rates of combustion. Higher rates of combustion would be beneficial if the reduction in furnace size and cost and in building volume were to offset the increased costs of operation. The present rates are set by the troubles encountered with ash and to a lesser extent the losses resulting from incomplete combustion. Overall performance figures have been of value but are no longer of great use in solving design problems because the relation of the average to the maximum is not known or not rationalized. We must know, for instance, how to conclude from the average temperature of the gases leaving a furnace and the furnace geometry what is the maximum temperature existing within the furnace cavity and the point at which it exists. Failures of pressure parts and troubles from intense heat release do not average out over an area or throughout a volume but only over a small part of the area or within a small part of the volume. The average condition is no more indicative of the maximum than the average wind velocity in a country is indicative of conditions in the heart of a cyclone within that country. We must, therefore, develop through research our technique of measurement to permit the advances in theory required before design can be improved.

Higher Rates of Combustion

Present methods of burning solid fuels on grates and in suspension, and of burning liquid fuels, clearly show differences in intensities which indicate that we are now burning fuels at rates in "hot spots" which if possible on the average would make the furnace volumes comparatively minute. Conversely, if the present averages were maintained and the variations between maximum and minimum rates were leveled out many of the existing "hot-spot" troubles would disappear.

The writer has made tests of boilers fired by pulverized coal in water-cooled furnaces in which average heat release rates of 25,000 to 30,000 Btu per cu ft per hr were easily obtained and maintained. Similarly, tests of boilers with small refractory-lined furnaces fired with oil have been made just as readily with average heat release rates of 175,000 Btu per cu ft per hr. Rumors of tests involving release rates with oil fuel over twice this latter value have been heard, and direct-fired air heaters using oil have been reported as burning millions of Btu per cubic foot. Tests made by the writer on Coxe stokers burning anthracite have shown it possible to sustain rates of combustion as high as 50 lb per sq ft of grate per hour, equivalent to 150 lb or 1,700,000 Btu fired per cu ft of fuel bed per hour. Not all of this heat was released in the bed, the analyses of the gases at the top of the fuel bed showed that some was released by gaseous combustion within the furnace. Considering the fuel bed as a gas producer, producing a gas rich in CO, we can assume that this value should be reduced to about 850,000 Btu per cu ft of fuel bed per hour.

The point is that very high rates of combustion are readily obtained with liquid fuels not associated with ash and in beds of solid fuel not disrupted by air flow. The almost fantastically high figures estimated for fuel bed release rates suggest a "hot spot" to average ratio of thirty or forty to one which makes one question the significance of the corresponding average value for the entire furnace. Few data are available on the variation in the intensity of combustion in the furnace cavity but no one will deny that large variations exist and, therefore, the average does not indicate the maximum. The aim should be to find what conditions exist at the "hot spot" in the furnace and how we may increase the volume of the "hot spot" until it fills the furnace; and thus bring the average rate of heat release to at least the value which exists at some point in the furnace today or, conversely, how indicated maximum intensity may be brought down while keeping the average the same.

Part of the problem of higher rates of combustion or the elimination of "hot spots" is the effective use of the available furnace volume. In marine boiler tests it has been found that the rotary motion imparted to the air by registers on oil burners was dissipated very quickly in rectangular furnaces but persisted in the cylindrical furnaces of a Scotch marine boiler. From this, and other indications, it can be concluded that the shape of a furnace has an important influence on the effectiveness of mixing. It is fair to assume, from available observations, that some shapes of furnace permit the formation of more eddy currents than others and the initial energy of the fuel and air streams is dissipated by these eddy currents. Furnaces are now shaped to fit available space and to comply with certain obvious requirements of

* A paper before the Midwest Power Conference, Chicago, April 13-14, 1944.

practical and economic construction. From considerations of the change of kinematic viscosity of gases with temperature it seems likely that we must be prepared to use energy much more freely in large furnaces to secure the same degree of turbulence as is now obtained in small furnaces. This relation of the factors controlling the ability to secure thorough mixing of the fuel and air for combustion is at present entirely on an empirical basis and should be rationalized by research.

Oil fuels are being burned in furnaces under pressures of five or six inches of water quite generally and we may learn, after the war, that pressures measured in pounds have been used, as is the case in the Velox boiler. Increasing the number of oxygen molecules within a given volume by increasing the furnace pressure ought to increase the opportunity of collision with fuel particles and, therefore, the intensity of combustion. The answer may be partly known and may be made available later; but even though the answer has been found for liquid or gaseous fuels its application to solid fuels will probably be subject to modification because of the ash content.

The British Coal Utilization Research Association in its report on the "First Five Years" states that "By measuring the energy of its interaction with methyl alcohol it was established that coal substance is so finely structured that the surface accessible to oxygen molecules ranges from 100,000 to more than a million square feet per pound according to its rank." This seems large but it is probably small if compared to well-atomized oil. The problem, therefore, is not essentially one of providing contact surface in the fuel but of utilizing more effectively the contact surface provided by nature. The more effective utilization of this contact surface may come about by crowding more oxygen molecules into the small spaces; that is, by increasing pressures in the combustion chamber. The extra cost of the structural changes necessary to resist these pressures will be at least partly offset by the decreased size of the furnace. At any rate, full-scale experiments are not economically feasible and small-scale laboratory work should be undertaken.

Loss in Reactivity with Anthracite

Those who have burned anthracite have been interested in, and perhaps annoyed by, the particles carried out of the furnace in suspension in the gases. Some of us have tried to burn these particles and found it difficult. The above-mentioned report points out that "The marked decay in reactivity shown by anthracite when heated had been investigated. This property renders the relighting of partly consumed anthracite peculiarly difficult. The effect was traced to a loss of 'inner' surface (accessible to oxygen) when the fuel is heated above 800 C." If the reactivity of the unconsumed portion of a solid fuel decreases during the burning progress, what is the extent of the decrease and what factors affect it? It seems reasonable to expect some decay in reactivity of the fuel as it burns because the most reactive portion would naturally be the first consumed. Some change of this character may account for the necessity of assigning a large part of the volumes of existing furnaces to the combustion of the last portions of solid combustible in comparatively quiescent zones. In such zones mixing action is at a minimum and probably the reactivity is low, both factors working against the

reduction in furnace volume. Perhaps when measurements of reactivity are made on representative samples of the fuel in the progress of its combustion it will be possible to apply energy for mixing as needed and thus maintain "hot spot" burning rates in what are now quiescent zones of the furnace.

In any consideration of combustion in fuel beds a very obvious point is that the fuel is in large enough particles so that it is not floated on the air stream. Under such conditions the scrubbing action of the air against the surface of the incandescent fuel is a maximum and reaction is rapid. Much work on fuel beds has been done. Henry Kreisinger did some pioneer work at the Bureau of Mines on combustion in fuel beds and pointed out that all oxygen would be consumed from the air passing through a bed of incandescent fuel four inches or more in thickness. The significance of this work on fuel beds is that it is theoretically and practically impossible to supply sufficient air for combustion through those sections of the fuel bed composed of a thickness of four inches or more of uniform incandescent fuel. Obviously, the deficiency in air must be made up through other portions of the fuel bed which are not completely ignited or which are burned out. The streams of gases deficient in oxygen must be mixed with those rich in oxygen either by providing time and volume enough for diffusion, or by compulsion in the form of arches. Arches can work perfectly only at the rate of combustion or flow of gases for which they are designed. At other rates some assistance must be given in the form of steam or air jets to provide the mixing.

Jets vs Arches

In 1924 the writer reported a study of "Combustion of Anthracite on Coxe Stokers" in which steam jets were used to simulate the action of a rear arch. The results, using steam at 150 psi, were approached but not equalled by the arch. If air jets are used the air must have sufficient energy to penetrate the gas streams and supply the needed oxygen. The spur for research along the lines of combustion in fuel beds is the high volumetric heat release rates obtainable in fuel beds and the comparative ease with which high release rates may be obtained in the combustion of the gases rising from the bed. The desirable condition is the maximum turbulence of the air and gases passing through the fuel bed, obtainable without disruption of the bed, together with energetic mixing devices and air supply in the furnace above the grates to insure rapid gaseous combustion. Perhaps some combination of combustion on grates, in suspension, and gaseous combustion will be indicated as the most economically efficient use of available volumes.

Radiant Heat Absorption

In the study of combustion with emphasis on the factors affecting higher rates, the rate of loss of heat from the flame is of importance. Most large units are designed with some arrangement of water cooling at the envelope of the furnace and this cold surface absorbs heat as a function largely of the emission temperature and the black-body volume of the flame. Except in furnaces having a high degree of turbulence the convective component of absorption is small. At present it is quite generally the practice in estimating the emission temperature of furnaces gases to assume it to be the same as

the average temperature of the gases leaving the furnace cavity. This assumption is safe enough for a furnace which does not approach limiting conditions at the "hot spot," but is questionable when it is known that wide variations exist within the furnace cavity and that the maximum may subject the cooling means at some point in the envelope to a strain beyond its limits. Here again, the relation of the temperature of gases leaving a furnace to the emission temperature of the gases within the furnace should be studied with emphasis on the maxima and measuring devices are needed. John Blizard pointed out in his recent paper on "Absorption of Heat by the Walls of a Furnace" before the A.S.M.E., that the amount of heat absorbed in a cooled furnace was found to be related to the rate of firing. Under his conditions most of the heat was transmitted by radiation and his findings are of interest, in indicating that the black-body volume of the flame changes with the rate of fuel consumption. Temperatures of the flame, at the different rates, varied somewhat because of minor variations in CO_2 but not sufficiently nor consistently enough to explain the variations in the quantity of heat absorbed. Although the trend in large utility units seems to be toward operation at nearly constant loads, a sufficiently large number of units will be needed for operation at varying loads to make the determination of the relation of black-body volume of flame to fuel consumed and to furnace geometry an important research project.

Cooling the Furnace Envelope

If research rationalizes the manner in which higher liberation rates may be obtained, as well as more effective use of available volumes, it must also solve some related problems having to do with the design and cooling of the furnace envelope. Paradoxically, the liquid phase of water has been shown to be less effective as a cooling medium than the mixture of liquid and vapor phases at a slightly higher temperature. Work on the transmission of heat to boiler tubing at high pressures¹ reported the empirical conclusion that the film resistance under evaporating conditions was negligible as compared with the resistance of the metal of the tube; but in the absence of vapor the film resistance was found to be appreciable. The low film resistance is believed to depend on the disruption of the liquid film during the formation and escape of vapor bubbles. Assuming the relative unimportance of the film resistance under evaporating conditions as compared to the resistance of the metal of the tube Dr. Jacob, in a discussion of this paper, computed the tube surface temperatures at certain rates of heat absorption and thus confirmed the conclusion.

Assuming, then, that the furnace cavity will be cooled by evaporation, how can the resistance due to tube wall thickness be reduced, particularly at high pressures other than by decreasing the tube diameter? In long small tubes, as are practicable in forced-circulation boilers, the sum of the radiation and convection components in a furnace having an extreme degree of turbulence and a high rate of heat release may produce tube surface temperatures 150 F above saturation.

¹ "Studies of Heat Transmission Through Boiler Tubing at Pressures from 500 to 3300 Pounds," by P. H. Hardie, C. G. R. Humphreys, A. A. Markson, A. R. Mumford and T. Ravese, A.S.M.E. Transactions, August 1943.

Ely and Schueler² have reported the failure of a thick wall tube due to temperature stresses alone even with adequate circulation of the cooling medium. This indicated that, at that location, the stress produced by the temperature differential through the metal exceeded the resistance of the metal to stress and the rate of heat transmission had to be decreased. What are the temperature drops through available alloys and what is the relation of these drops to those found for carbon steel of the same strength? As operating pressures approach the critical it is apparent that the amount of heating surface devoted to evaporation will decrease and the proportion devoted to water heating and superheating will increase. At the critical pressure no evaporating surface is required because of the absence of latent heat and the boiler will then consist of a water heater and a superheater. It should be an interesting problem to determine the disposition of heating surface so that the change in the cleanliness factor of the furnace will not upset the designed balance of the heating surface or will not completely preclude operation at more than one load. The amount and distribution of the heating surface must be based on a knowledge of the rate at which heat is released and available as well as the mechanism by which it is transmitted to the liquid. At low steam pressures, the ability of a tube to absorb heat was seldom, if ever, questioned but now we need to know more of the limits of such absorption because they are being approached.

Ash Behavior

It is generally recognized that ash is always a nuisance and sometimes constitutes an operating problem. The degree of the nuisance or problem differs with the quantity or the physical properties of the ash and sometimes with both. The ashless fuels, oil and gas, do not constitute a sufficiently large proportion of our fuel reserves to warrant any optimism that they will remove, by substitution, the obstacle that ash now constitutes in obtaining higher rates of combustion. Furthermore, 75 per cent of our solid fuel resources are in the central and western fields which are likely to contain appreciably more non-combustible material than the eastern. It seems obvious that any problems introduced into the burning process by the presence of non-combustible material are likely to increase as our resources decrease. For this reason and because the ash in coal is now much more of a problem than an annoyance, research should be directed toward its amelioration.

The two principal problems introduced into the combustion of solid fuels by ash are the insulation of heat-absorbing surfaces and the obstruction of gas passages. Heat-absorbing surfaces are insulated by the adherence of particles of ash that form a layer varying in thickness in accordance with the physical properties of the ash. The more refractory the ash the less the trouble to be expected, assuming that the present laboratory measurements of softening and fluid temperatures are indicative of the viscosities involved. The result of this insulation is to disturb the design balance between evaporating and superheating surfaces and this necessitates changes in operating procedure to restore the desired conditions.

² "Distribution of Heat Absorption and Factors Affecting the Performance of the Twin Branch 2500-psi, 940-F Boiler with Reheat to 900 F," by E. G. Ely and L. B. Schueler, A.S.M.E. Annual Meeting, December 1943.

When the layer of ash deposits on adjacent boiler tubes between which the gases are flowing, the layer may build to a thickness which will materially increase the draft loss or completely obstruct the flow thus necessitating reduction of rating until the obstructions are removed. Minor problems are introduced by the variation of the relation between viscosity and temperature affecting the removal of ash as a fluid from furnaces.

Ash also has some chemical properties. We believe that the chemical properties of the ash are responsible for the loss of metal from furnace tubes under the conditions of gas composition existing in parts of the furnace. This particular reaction is being studied in the laboratories of the Bureau of Mines in Pittsburgh under a cooperative agreement. When this investigation reveals the fundamental reactions involved, the control of the reactions will be apparent.

Relating Laboratory Measurements to Field Conditions

The pioneers in the field of ash softening, fusion and liquid temperatures are today in the forefront of those recognizing the need for new studies of the physical properties of ash. Much work has been done but more is necessary to relate laboratory measurements to field conditions. At present certain physical properties can be predicted from a knowledge of the chemical composition of the ash but until more is known of the actual conditions to which the ash is exposed in the furnace the greater part of the value of this information will remain potential. If, however, the conditions of exposure are determined and related to the geometry of the furnace and the firing rate and method, it is not too optimistic a prediction to say that it should be possible to estimate the location and thickness of deposits and infer the resultant effect on heat transfer from our knowledge of the black-body volume and the emission temperature of the flame and the physical properties of the ash. There is uncertainty at this time whether the conductivity of slag varies with its chemical composition, but a study of this property is under way at the Bureau of Mines under the above-mentioned cooperative agreement. The results of this study will indicate whether chemical composition can be eliminated from consideration in determining the insulating effect of the layer of slag and hence consider only its thickness and its particular physical structure.


The effect of physical structure will be studied by relating the laboratory results to field conditions. The thickness of the deposit will obviously vary with the conductivity of the ash, thus an ash having a high resistance to the flow of heat will become fluid at the surface in comparatively thin layers. To relate the laboratory work to field conditions the heat flow must be measured by existing temperature drop methods and instruments developed to measure the furnace side surface temperature of the slag layer. Without a more complete knowledge of the physical properties of ash any attempt at eliminating it, as one of the factors preventing the attainment of higher rates of combustion, must be almost entirely empirical and probably costly. With more knowledge the designer can make some provision in his design to fit it to the predicted conditions for the case under consideration.

It is known that the combustible substance of coal is, in general, less dense than the non-combustible sub-

stance. Separations have been made by flotation and the heavier fractions found to contain the larger proportions of non-combustible material. Coal washing is practiced at some mines but only where the ash content of the original product was considerably higher and more troublesome than that of competing coals. Some users have justified the cost of cleaning by reduction of operating costs in existing installations. There is evidence also that the cost of cleaning is not justified when the furnace can be designed to handle the uncleaned fuel. At any rate more knowledge of the properties of the ash will permit the formation of conclusions with greater assurance.


Conclusion

The writer has endeavored to point out the necessity for fuel research and the lines it might take. To accomplish two general objectives, (1) increasing the combustion rates and (2) amelioration of troubles from ash, we must develop and use instruments to measure local conditions within the furnace cavity or fuel bed, and the physical and chemical properties of the ash. We should no longer predicate extrapolated performance on existing average conditions but should study the maxima in detail. Dr. Carl B. Boyer in his *History of the Measurement of Heat* said "As science goes on in the search for still greater unity, let it be remembered that the way is paved, not with unmeasured speculation, but with the objective data of patient quantitative research."



The submarine represents the most concentrated power known to naval warfare. Similarly, the IMO oil pump provides great concentration of pumping capacity in small space. It is extremely compact, rugged, simple and reliable, having only three moving parts and no valves or pilot gears.

The IMO oil pump is used on submarines for pumping both fuel and lubricating oils. You can use this small, but effective, pump for handling oil of practically any viscosity, in any volume, and at any pressure. Ask for Leaflet I-112.




ULTRA-MODERN WATER CONDITIONING

Using Latest Design Cochrane Equipment—

In this, one of the most carefully designed boiler plants constructed in recent years, a Cochrane Hot-Process Water Softener of 80,000 GPH capacity is used for the water treatment, using lime soda and supplementary phosphate. Six Cochrane anthracite filters are also used, and a Cochrane Deaerator of 620,000 lbs./hr. capacity. Two electrically operated proportioners with two chemical tanks operated from Cochrane

controls on panel board are also part of this installation.

Complete details of this and many other modern boiler plant installations will be furnished on request.



COCHRANE CORPORATION



3109 N. 17th ST., PHILADELPHIA 32, PA.

COCHRANE

SOFTENERS • DEAERATING SOFTENERS • DEAERATORS • METERS • STEAM SPECIALTIES

High-Pressure and High-Temperature Steam for Marine Use

The following discussion before a meeting of the Metropolitan Section, Society of Naval Architects and Marine Engineers, on April 28, 1944, reviews advances in marine steam generation with particular reference to forced circulation, several designs being shown of such boilers that are in actual service.

WITHIN the past decade marine boiler designs have undergone a pronounced development. Perhaps this change would have been even more notable if not affected by the mass-production program of the Navy and the Maritime Commission. However, it is anticipated that post-war competitive shipping conditions will witness a continuation, even an acceleration, of such improvements in marine boilers for better economy of ship propulsion. In this trend higher pressures and temperatures are sure to play a leading role.

Marine boilers for the generation of steam at high pressure and temperature have always been of major interest due to the inherent savings possible. The designs developed in this field are based on a background extending back to the shipbuilding program of World War I and reflected in a wide participation in the present shipbuilding programs of the Maritime Commission and the Navy, and enhanced by a broad experience in this field in stationary work.

Generation of steam at present high pressures and temperatures can no longer be considered experimental. Reliability is a matter of perfection in detail of design, manufacture, and erection rather than of the type of plant. Any consideration of high-temperature and high-pressure steam should receive due concern with respect to turbines, to auxiliaries, and to water treatment, as well as to the boilers. Progress in the development of these equipments has kept in step to a surprising degree. Although at times one may have progressed more rapidly than another, any tendency to lag has been quickly overcome.

As a result we find today in turbines, auxiliaries and boilers tried and proved designs from all standpoints. This is true of materials, methods of construction, capacities and methods of operation. Many lessons learned in shore plants are directly applicable to shipboard plants. Materials suitable for sustained operation at temperatures of at least 950 F are well known, and it is anticipated that alloys suitable for even higher temperatures will be available in the near future. The adoption of welding has been widespread especially as applied to boiler drums and steam piping. Knowledge has been gained to allow provision of proper thicknesses of tubes and drums without setting up excessive stresses arising out of differential expansion associated with high rates

By W. H. ARMACOST, Vice President
Combustion Engineering Company, Inc.

of heat absorption. Feedwater treatment aboard ship is simplified due to low distilled makeup required.

The accompanying illustrations show a range of recent designs.

The boilers shown in Fig. 1 are installed in large combination passenger and cargo ships. There are four per ship, each having a normal capacity of 40,000 lb of steam per hour at 600 psi gage and 840 F.

Fig. 2 duplicates in nearly all respects that shown in Fig. 1, except the shape of the furnace is modified to fit a differently shaped fire room space.

Fig. 3 and the one following are designs brought out about five or six years ago. It was designed for 1215 psi and 750 F at the superheater outlet, and a capacity of 32,000 lb of steam per hour. The efficiency is about 86 per cent. The separately fired furnace is to provide controlled reheat.

The design in Fig. 4 was developed at about the same time as that in Fig. 3 and was designed to generate 31,000 lb of steam per hour at 1300 psi and 960 F at the superheater outlet. The feedwater temperature is 400 F and the efficiency 88 per cent.

A number of boilers of the type shown in Fig. 5 are now under construction and are to be installed shortly in new ships. The design pressure is 1535 psi, for operation at 1460 psi and 750 F. The capacity is 50,000 lb of steam per hour. This provides also for two stages of steam reheat. Its features are as simple as for lower pressures, showing that higher pressure and temperature can be used without additional complication.

The following table is based upon R. H. Tingey's paper, on "High-Pressure Steam for Marine Propulsion," presented last October before the New England Association of Naval Architects and Marine Engineers.¹ It indicates the magnitude of the gains that may be achieved with pressures up to 1450 psi and temperatures up to 950 F.

Pressure and Temp.	Approx. Per Cent Fuel Reduction
450-750	0
600-850	6
900-900	10
1450-950	13
1450-750 (1 steam reheat)	9
(2 steam reheat)	11
1450-750 (1 gas reheat)	11

Additional gains of lesser magnitude may be secured by temperatures and pressures higher than 1450 psi and 950 F, but higher pressures will require boilers of greater height, perhaps in many cases more than can be afforded by the naval architect, if the natural circulation boiler is adhered to. Otherwise, the obvious difficulties due to

¹ Reprinted in the January and February 1944 issues of COMBUSTION.




Fig. 1




Fig. 2




Fig. 3




Fig. 4




Fig. 5

SOME RECENT DESIGNS OF NATURAL CIRCULATION MARINE BOILERS

inadequate circulation will arise. Such handicaps may, however, be overcome by the forced-circulation boiler. Higher temperatures will await the availability of the suitable war-developed alloys, information respecting which is now obtainable. Such alloys will also be a product of the intensive development now being expended on the gas turbine. Thus, it is felt improvement in gas-turbine cycles will result in corresponding improvement in steam-turbine cycles.

Up to about 1500 psi, boiler construction does not depart radically from previous practice. Tube banks may be arranged for satisfactory heat absorption and still permit drum tube plates of reasonable thickness. Above 1500 psi, complications arise with thick tube plates, or on the other hand, wide tube spacing and lower heat absorption must be used. Under 1500 psi, conventional natural-circulation designs are adequate to meet the problems presented. The ratio of the density of water with respect to the density of steam measures the rate of circulation in a natural-circulation boiler. Above 1500 psi this ratio decreases very rapidly. Thus, higher boilers are necessary to provide enough 'head' for sufficient circulation to prevent damage

to tubes subjected to high rates of heat absorption. Under most conditions aboard ship, such height is unobtainable.

The controlled forced-circulation boiler is a simple solution to this problem. Through the use of positive circulation extremely wide flexibility of design is possible, making the boilers readily adaptable to limited and oddly shaped spaces. It also permits arrangement of heating surfaces to best advantage. Operation of controlled forced-circulation boilers, like natural circulation, does not require intricate controls. Furthermore, the forced-circulation principle allows the boilers to be put on and taken off the line very rapidly. Extreme load changes affect water level very little.

The following illustrations show the application of forced-circulation boilers over a wide range of pressures, temperatures and capacities, from as low as 20,000 lb of steam per hour to 650,000 lb of steam per hour, from 290 psi to 2000 psi and from 690 F to 950 F.

Fig. 6 represents a controlled forced-circulation boiler having a capacity of 120,000 lb of steam per hour at 290 psi and 690 F. It is included merely to indicate the complete range of temperature, pressure, and type of service to




Fig. 6




Fig. 7




Fig. 8




Fig. 9

CONTROLLED FORCED-CIRCULATION MARINE BOILERS FOR WIDE RANGE IN PRESSURE




Fig. 10




Fig. 11

TWO LARGE FORCED-CIRCULATION UNITS INSTALLED IN STATIONARY PLANTS

which controlled forced-circulation boilers are applicable.

The boiler in Fig. 7 is designed to operate at 500 psi, with a steam temperature of 800 F and is shown to indicate the flexibility in design when forced circulation is used. The capacity is approximately 26,500 lb per hour. This unit has been operating satisfactorily over a period of several years.

Fig. 8 shows a controlled forced-circulation boiler specially designed to fit into an extremely restricted fire room space. The capacity is about 20,000 lb of steam per hour at 900 psi and 850 F.

Fig. 9 represents another special design of forced-circulation boiler for 1200 psi and 900 F with a separately fired superheater for complete control of superheat. The maximum capacity is in excess of 200,000 lb of steam per hour.

Fig. 10 shows a large unit which operates at a capacity of 400,000 lb of steam per hour at 700 psi and 750 F, and Fig. 11 is a unit operating at 1825 psi (2000 lb design) and 960 F. It has a capacity of 650,000 lb of steam per hour. These last two are installed in stationary plants and are included merely to show the present range in capacities of forced-circulation units.

All of these forced-circulation boilers have been built and are in operation.

Following the present period of restrictions on the use of materials there is a feeling in some quarters that extensive use in shipbuilding will be made of lightweight metals and alloys. When this develops, the weight of the boiler begins to assume a new importance. Forced-circulation boilers can be made lighter than natural-circulation boilers, particularly where higher steam pressures are involved.


Carey HEAT INSULATIONS



Carey Heat Insulations
For temperatures up to
800° F.



85% Magnesia
For High and Medium
Pressure.




Combination Hi-Temp—
85% Magnesia.

Cut Production Costs


Modern industrial plants are saving thousands of fuel dollars each year through the correct application of CAREY Heat Insulations . . . a complete line of high efficiency insulating materials of Asbestos and Magnesia for every known service condition—for temperatures ranging from

SUB-ZERO to 2500° F.

Put your special problems up to Carey Engineers . . . their experience and Carey research facilities are available through branch offices covering the nation. Write for book of interesting technical data. Address Dept. 69.



Hi-Temp Blocks—For Furnaces, Ovens, Kilns, etc.



Wool Felt Insulation
For sub-zero.

THE PHILIP CAREY MFG. COMPANY

Dependable Products Since 1873

Lockland, CINCINNATI, OHIO

In Canada: The Philip Carey Co., Ltd.

Office and Factory: Lennoxville, P. Q.

Industrial Power Requirements

A COMPREHENSIVE report has just been issued by the Federal Power Commission dealing with "Electric Power Requirements of Industrial Establishments." Actual figures are given for the period 1939-1942, inclusive, which are extended to 1944, based on estimates reported for over 90 per cent of all electricity consumed by manufacturing and extracting industries in the United States as well as government-owned establishments, such as arsenals, etc. The term "extracting industries" is applied to mining of all kinds, petroleum and natural gas. Of the total of 21,235 establishments reporting for 1943 the estimated electric requirements were nearly 156 billion kilowatt-hours divided as follows:

Classification	Electricity Requirements of Reporting Establishments, 1943 (Thousands of Kilowatt-hours)	Number of Reporting Establishments
Manufacturing	141,491,569	18,475
Extracting	9,149,642	2,399
Government	5,306,903	361
Total	155,948,114	21,235


Figures for 1939-1942, extended to 1944 and covering over 21,000 reporting establishments, show that industrial use of electricity has more than doubled during the last five years. Of this, purchased electricity increased nearly three times and that privately generated was up 66 per cent. Load factors were considerably higher for the latter.

The reporting establishments are classified in accordance with the 1939 Census of Manufacturers; that is, on the basis of the principal products manufactured during peacetime. Although considerable conversion of industrial production has taken place since this country entered the war, this has applied largely to products rather than to the particular industry, so

that reclassification into other groups has not been necessary. The chief exception has been the automobile industry which is now engaged extensively in making aviation products; although it is still turning out much automotive equipment such as trucks, jeeps, armored cars and tanks.

Table 1 represents electricity requirements of reporting establishments by major industry groups for 1939-1944. From this it will be seen that the industrial use of electricity has more than doubled in the last five years.

Purchases of electricity by the firms reporting were placed at 108 billion kilowatt-hours in 1943 and 119 billion kilowatt-hours estimated for 1944. The sum of the non-coincident demands for purchased power was placed at 22.9 million kilowatts for 1943 and 23.5 million kilowatts for 1944. Generation by the reporting establishments was estimated at 51 billion kilowatt-hours for 1943 and 53 billion kilowatt-hours for 1944. The capacity of generators, exclusive of motor-generator sets, was indicated to be 11.8



million kilowatts at the end of 1943. Table 2 gives these figures for the years 1939-1944. From this it will be apparent that most of the increased use of electricity for industrial purposes has been supplied by the electric utilities. Purchased energy for 1944 was estimated as nearly three times that of 1939, whereas

From the above it will be seen that the annual load factor for purchased energy is expected to rise from 40 per cent in 1939 to 58 per cent in 1944, a rise of 18 points, whereas the average load factor for generation is expected to increase 12 points during this period. While these figures represent an average, the annual load factors in-

creased in all the major industry groups, except two. For example, in the automobile and transportation groups the load factors of electricity purchased increased from 28 to 51 per cent, and from 26 to 55 per cent, respectively; and those for energy generated increased from 40 to 57 per cent and from 22 to 34 per cent, respectively. Load factors in the chemical and non-ferrous metal groups, which were relatively high in 1939 (55 and 58 per cent, respectively) also had notable increases to 77 and 80 per cent.

The accompanying chart shows the industrial use of electricity among the classified groups, proportionately arranged for geographic divisions of the country.

In the area east of the Mississippi River the estimated requirements for 1944 are 123 billion kilowatt-hours, or three-fourths of those for all the reporting establishments in the United States. The East North Central division shows the greatest use, followed closely by the Middle Atlantic division. The largest growth in electricity consumption for the period covered was in New York State, with 10 billion kilowatt-hours. California, Ohio, and Pennsylvania each increased approximately 7 billion kilowatt-hours. The largest increases in per cent were in Nevada where industrial use of power in 1944 is expected to be almost fourteen times that used in 1939, and in Arkansas where the use in 1944 is expected to be eight times that in 1939. These increases are, of course, largely attributed to war loads.

TABLE 1—ELECTRICITY REQUIREMENTS OF REPORTING ESTABLISHMENTS BY MAJOR INDUSTRY GROUPS 1939-1944 (In Order of 1944 Estimated Consumption)

Industry Group	Thousands of Kilowatt-Hours					
	1939	1940	1941	1942	1943	1944
Manufacturing industries:						
Chemicals	9,356,998	12,029,304	15,603,840	20,572,432	28,929,840	31,859,753
Non-ferrous metals	6,085,358	7,921,793	10,551,754	15,255,157	23,973,889	28,901,486
Iron and steel	12,781,648	15,410,043	19,445,380	20,981,457	24,275,320	25,192,502
Paper	9,462,556	10,480,187	11,728,043	11,786,616	11,924,661	11,980,422
Textile	6,272,654	6,794,130	8,417,166	9,016,242	9,256,725	9,278,018
Transportation equipment	493,310	797,086	1,635,927	4,246,279	7,099,456	8,071,418
Stone, clay and glass	4,503,209	4,969,940	6,119,863	6,436,579	6,073,439	5,978,431
Food	4,521,733	4,591,818	5,128,200	5,508,056	5,891,692	5,970,138
Petroleum and coal	3,111,936	3,442,194	3,859,441	4,039,664	4,813,565	5,753,495
Machinery, except electrical	1,805,704	2,322,262	3,295,827	4,448,822	5,455,951	5,672,008
Automobiles	2,432,205	2,991,733	3,610,045	3,404,618	4,458,042	4,590,838
Electrical machinery	1,392,951	1,761,289	2,441,703	2,918,404	3,526,086	3,747,589
Rubber	1,557,227	1,631,208	2,029,387	1,742,699	1,978,409	2,034,946
Lumber	1,132,235	1,264,068	1,406,424	1,478,662	1,521,217	1,525,728
Miscellaneous	339,803	382,167	504,280	629,232	781,873	810,939
Furniture	412,043	466,561	551,277	569,675	600,657	604,609
Leather	294,516	297,335	356,663	377,345	377,585	373,409
Printing	289,933	308,946	335,750	338,618	344,056	346,165
Tobacco	81,255	88,435	97,307	105,196	107,527	108,432
Apparel	72,585	78,060	92,996	99,878	101,779	102,673
All manufacturing	66,399,859	78,028,529	97,211,291	113,965,431	141,491,569	152,902,999
Extracting industries:						
Coal mining	3,035,015	3,420,799	3,655,573	4,176,481	4,552,160	4,617,680
Metal mining	1,993,912	2,296,788	2,606,675	2,945,320	3,168,922	3,234,810
Non-metallic mining	536,477	593,317	746,321	797,457	809,118	805,994
Petroleum and natural gas	549,001	605,903	602,405	594,743	619,442	619,050
All extracting	6,114,405	6,916,807	7,610,974	8,514,001	9,149,642	9,277,534
Government	609,688	835,131	1,476,199	3,182,736	5,306,903	5,983,123
All industries	73,123,952	85,780,467	106,298,464	125,652,168	155,948,114	168,163,656

privately generated energy was expected to increase only about 66 per cent.

It will be observed further from this tabulation that the generating capacity owned by reporting establishments increased 21 per cent from 1939 to 1943.

TABLE 2—ELECTRICITY REQUIREMENTS OF REPORTING ESTABLISHMENTS 1939-1944 Billions of Kilowatt-Hours and Millions of Kilowatts

Year	Purchases, Kwhr	Generation, Kwhr	Generating Capacity, Kw
1944	119	53	...
1943	108	51	11.8
1942	83	46	11.2
1941	68	41	10.5
1940	52	36	10.0
1939	43	32	9.7

The increasing intensity of use of industrial generating capacity resulting from increasing war loads is reflected in the following annual plant factors:

1939—37 per cent
1940—41 per cent
1941—45 per cent
1942—46 per cent
1943—49 per cent

The relationships between kilowatt demand and kilowatt-hours, for both purchased and generated energy in terms of load factors, are as follows:

	Annual Load Factors, Purchases, Per Cent	Annual Load Factors, Generated, Per Cent
1939	40	52
1940	43	55
1941	48	58
1942	49	60
1943	54	62
1944	58	64

Let ONE man take care of your COAL STORAGE PROBLEMS

If you have a man power shortage, let one man be responsible for storing and reclaiming coal—safely—rapidly—economically—with a Sauerman Scraper System.



Sauerman Scraper System handles 165,000-ton storage pile, a 300-day supply for this Michigan generating station.

Consider these advantages:

1. Maximum tonnage stored on all available space.
2. Operation is smooth and rapid.
3. Costs only a few cents per ton to handle.
4. Eliminates excessive dust and dirt.
5. Stocks in compact layer—no air pockets to promote spontaneous combustion.
6. One man operates with one set of automatic controls.
7. Low original cost to install.
8. Simple and economical to maintain.

The complete Sauerman Catalog is yours for the asking.

SAUERMAN BROS., Inc.

550 S. CLINTON ST., CHICAGO 7, ILL.





High grade gas, by-product and steam coal from Wise County, Va., on the Interstate Railroad.



High grade gas, by-product, steam and domestic coal from Wise County, Va., on the Interstate Railroad.



High grade, high volatile steam and by-product coal from Wise County, Va., on the Interstate Railroad.



A laboratory controlled product blended to meet exacting stoker requirements. From Wise County, Va., on the Interstate Railroad.

COKE

Roda and Stonega from Wise County, Va., and Connellsville Coke from Pennsylvania.



Our personnel with the experience gained through long and varied marketing activity assures effective servicing of any fuel requirement.



High grade gas, by-product, steam and domestic coal—Pittsburgh seam from Irwin Basin, Westmoreland County, Pennsylvania, on the Penna. Railroad.



Genuine Third Vein Pocahontas from McDowell County, W. Va., on the Norfolk & Western Railroad.



Genuine New River Smokeless, Beckley or Sewell seam from Raleigh County, W. Va., C. & O. and Virginian Railroads.



Hazard No. 4 and No. 7 steam and domestic coal from Wisconsin, Knott County, Kentucky, on the L. & N. Railroad.

GENCO

Steam and domestic coals from a number of producing districts.

ANTHRACITE—Hazle Brook Premium . . . Raven Run



General Coal Company

123 SOUTH BROAD STREET

PHILADELPHIA, PA.

Branches:

BLUEFIELD, W. VA.
CINCINNATI

BOSTON
DETROIT


BUFFALO
NEW YORK

CHARLESTON
NORFOLK

CHARLOTTE, N. C.
PITTSBURGH



POOLE



A COPY OF CATALOG GIVING FULL DESCRIPTION AND ENGINEERING DATA SENT UPON REQUEST.

FLEXIBLE COUPLINGS

POOLE FOUNDRY & MACHINE COMPANY

WOODBERRY, BALTIMORE, MD.

Alex Bailey Becomes Vice-President of Commonwealth Edison Co.

The Board of Directors of Commonwealth Edison Co., Chicago, have elected Alex D. Bailey Vice-President in Charge of Engineering and Operation, succeeding H. B. Gear who will retire from active service on June 30.

Mr. Bailey entered the Company's employ as a draftsman in 1903 and subsequently became chief engineer of the Fisk and Quarry generating stations, superintendent of generating stations and assistant chief operating engineer. He was made chief operating engineer in 1936 and assistant to Vice-President Gear in 1943. He was Vice-President of the American Society of Mechanical Engineers in 1936-37 and is Vice-Chairman of the Board of Trustees of Illinois Institute of Technology.


R. O. Muller Dead

Richard O. Muller, who recently retired as chief engineer of The Terry Steam Turbine Co., after 18 years in that capacity, died on June 4.

Mr. Muller had been identified with the steam turbine field practically all his adult life. Starting at an early age with Parsons in England, he later came to this country and was employed by E. W. Bliss Co. of Brooklyn as a turbine engineer. He joined The Terry Steam Turbine Co. in 1915 and became chief engineer in 1926.

HOW MUCH ARE YOU PAYING TO HANDLE ASHES?

You may be spending twice as much for ash removal as you need. Why not get full details on the money- and labor-saving Beaumont Birch "Vac-Veyor" pneumatic ash handling system. Write today for bulletin just off press.



BEAUMONT BIRCH COMPANY


1505 RACE STREET

PHILADELPHIA, PA.

DESIGNERS • MANUFACTURERS • ERECTORS OF COAL AND ASH HANDLING SYSTEMS

Make your new DISTRIBUTORS AN IMPROVEMENT

... not a replacement



Why repair old coal chutes when by replacing them with S.E. Co. CONICAL Coal Distributors you can eliminate coal segregation, improve combustion efficiency and increase stoker capacity? The CONICAL design of S.E. Co. Distributors eliminates faulty combustion and resulting stoker difficulties by delivering a uniform mixture of coal.


Before you repair or replace check with us... let us show you how S.E. Co. CONICAL Non-Segregating Coal Distributors can improve stoker operation. Stock Engineering Company, 9803 Theodore Ave., Cleveland, Ohio.

STOCK

CONICAL Non-Segregating Coal Distributors

ENGINEERING CO.

S.E. Co. Coal Valves and Coal Scales



Efficient combustion with **Enco Burners**

FOR ALL GRADES OF LIQUID FUEL

Enco Burner Units of Steam or Mechanical Atomizing Types are made in various sizes with capacities from 1 to 1000 gallons per hour.

Designed for operation either with or without air registers and for natural or forced draft.

The Enco Interchangeable Atomizer is made for instant change of guns for operation by either steam or mechanical system or to cover a wide range of capacity.

Enco Atomizers are used with various types and makes of pulverized-coal and gas-burner units to provide a dual fuel unit for cold starting, or for full-load operation when coal or gas is not available, or use when oil is the more economical fuel.

We have made many installations during the past 25 years and are ready to cooperate with those looking for better operation and assurance against loss of steam output.

THE ENGINEER CO.
Enco 75 West St.
New York 6, N. Y.

Electric Energy Demands Up

The Federal Power Commission announced on May 31 that April peak demands of the principal electric utility systems of the country aggregated 35,851,358 kw, an increase of 10.3 per cent above last year's April demand. Corresponding electric energy requirements amounted to 18,266,179,000 kw-hr, a gain of 8.3 per cent over April 1943. Comparable percentage increases reported for the preceding month were 10.3 per cent for demand and 11.0 per cent for energy in comparison with March 1943.

The Commission stated that estimates of December 1944 peak demands made by the Class I electric utility systems in their April reports amounted to 38,585,643 kw. Utility estimates of energy requirements for the year 1944 summarized from the same reports totaled 227,855,165,000 kw-hr. These estimates for 1944 indicate expected increases over 1943 of about 1,525,000 kw in December demands and some 12,735,000,000 kw-hr in annual energy needs. Such increases would represent gains of 4.1 per cent in demand and 5.9 per cent for energy.

The nameplate rating of new generating capacity placed in service during April totaled 254,080 kw. Scheduled net addi-

tions to the installed generating capacity of the principal systems are given as 871,500 kw by the end of 1944, and an additional 589,000 kw by December 31, 1945. These figures include only those additions actually on order and authorized by the War Production Board for installation in the year indicated.

A.B.M.A. Meet at Skytop

The largest attendance in many years characterized the 56th Annual Meeting of the American Boiler Manufacturers and Affiliated Industries, which was held at Skytop Lodge, Skytop, Pa., from June 4 to 7. The various sessions scheduled on the program were fully attended and the social activities, which are an attractive feature of these gatherings, helped considerably to the success of the meeting.

Officers elected for the coming year were: President—Albert C. Weigel, Combustion Engineering Company; Vice-President—Frank G. Brinig, Erie City Iron Works; and Secy. and Treas.—A. C. Baker.

More than the usual number of people participated in the golf tournaments and other programs, and the Annual Dinner was attended by 167.

NEW CATALOGS AND BULLETINS

Any of these publications will be sent on request

Conductivity Measurement

Leeds and Northrup Company has just revised its catalog, "Apparatus for Electrolytic Conductivity Measurements in Laboratory and Plant." This 44-page publication (EN-95 1944) presents much the same data about methods of measurement and notes for selection and use of the apparatus as did the previous edition, but in addition, it illustrates and describes a Signalling Conductivity Controller and several new industrial cells which have become available since the earlier edition was issued.

Coal Mine Directory

The Chesapeake and Ohio Railway has issued an attractive 55-page "Coal Mine Directory 1944" presenting useful information as to bituminous coal originating at mines in the region served by this railway. The Directory contains the following listings: 1—Operating Companies, showing mine name and number; 2—Mines, arranged alphabetically, showing item numbers and code numbers of railway stations; 3—Stations at which mines are located; 4—Geographical Arrangement of Mines, together with 5 full-page maps in color; and 5—Sales Agents. The book is spiral bound and a large folded map of the districts and fields served by the C and O Railway is included.

Insulated Pipe Units

The Ric-wil Company has issued a 6-page folder describing the latest improvements incorporated in its insulated pipe units. These comprise a new drive coupler for mechanical or welded conduit connection, a new pre-seal and a welded spiral lock seam running the full length of the conduit. The features of this prefabricated insulated-pipe conduit system are admirably illustrated.

Tube Cleaners

An interesting and colorful 24-page bulletin on Tube Cleaners has been issued by the Elliott Company. This admirably illustrated bulletin (Y-18) covers the entire field of modern practice in this equipment. Latest types of cutter heads and motors to which they are adapted are described. Large cutaway illustrations in color picture the interior construction of various motors driven by air, steam or water. Specialized tube cleaners and special applications for standard equipment are described.

Central Heating

A 6-page folder describing the many advantages of Central Heating for municipalities, large and small housing projects, hospitals and colleges and industrial groups, has been issued by The Ric-wil Company.

General and Classified Index

COMBUSTION, Volume Fifteen, July 1943 through June 1944

EDITORIALS—

	PAGE
A Constructive Research Project.....	Dec. 1943 27
A Forecast of Power Demand.....	Apr. 1944 31
A New Secret Weapon?.....	July 1943 27
Another Scrap Drive.....	Oct. 1943 29
A Tribute to Utility Cooperation.....	May 1944 27
Burning Mixtures of Bituminous Coal and Anthracite	
Fines.....	Mar. 1944 31
Censorship.....	July 1943 27
Collective Bargaining Within the A.S.C.E.....	Feb. 1944 27
Convention Curtailment.....	Aug. 1943 27
Disposal of Surplus Property.....	Mar. 1944 31
Engineering Training Under Government Supervision.....	Nov. 1943 33
Evaluating the Gas Turbine.....	May 1944 27
Extra Home-Front Tasks.....	June 1944 37
Gas Turbine, The.....	Dec. 1943 27
George A. Orrok.....	Apr. 1944 31
Less Coal Calls for Greater Vigilance.....	Nov. 1943 33
Limited Rationing of Bituminous Coal.....	Sept. 1943 27
Marine Engineers.....	Sept. 1943 27
Marysville.....	Oct. 1943 29
Meeting the Post-War Oil Demand.....	Feb. 1944 27
Overfire Air.....	July 1943 27
Patent System Vindicated.....	Aug. 1943 27
Power Trains.....	June 1944 37
F. H. Rosencrans.....	Sept. 1943 27
Salvaging Equipment for Technical Schools.....	May 1944 27
Semi-Outdoor Plants.....	June 1944 37
Significant Facts on Oil Demand.....	Dec. 1943 27
Station Heat Rates.....	Jan. 1944 29
Unpredictable Trends.....	Oct. 1943 29
Waste Chasers.....	Jan. 1944 29
Watch the Smoke.....	Apr. 1944 31

ARTICLES—

	PAGE
Addition to Capacity and Modernization of the Marysville Power House. By H. E. Macomber	
Part I.....	Oct. 1943 30
Part II.....	Dec. 1943 37
Part III.....	Feb. 1944 35
Part IV.....	Mar. 1944 39
Part V.....	May 1944 39
Adjustable-Blade Pumps, A.S.M.E. Spring Meeting at Birmingham. By J. D. Scoville.....	Apr. 1944 47
A.S.M.E. Annual Meeting, Steam Power and Fuel Problems Predominant at—Furnace Performance Factors, Performance at Twin Branch, Experiences at Chicago Stations, Boilers on Public Service System, Detroit Units Compared, Units in Three Philadelphia Stations, Heat Transfer Measurements, Measurements on Oil-Fired Unit, Flow Characteristics of Coal-Ash Slags, High-Temperature Steam Corrosion, Potassium Salts Replacing Sodium Salts in Boiler-Water Conditioning, Heat Rates for Theoretical Regenerative Steam Cycle, Combustion-Control Methods, Burning Barley Size Anthracite, Fuels and Fuel Research in Great Britain, Uses for Fly Ash, Boiler Fan Selection and Use, Notch-Toughness Tests of Carbon-Molybdenum Pipe, Combustion in High-Pressure Chambers.....	Dec. 1943 28
A.S.M.E. Spring Meeting at Birmingham.....	Mar. 1944 59
A.S.M.E. Spring Meeting at Birmingham—Stoker Fuel-Bed Studies, Oblique Radiation Boiler Tubes, Pulverizer Maintenance, Operation of Hydro and Steam Capacity, Adjustable-Blade Pumps.....	Apr. 1944 46
An Evaluation of the Importance of Physical and Chemical Properties of Fly Ash in Creating Commercial Outlets for the Material, A.S.M.E. Annual Meeting, By C. M. Weinheimer.....	Dec. 1943 35
A New Approach to the Problem of Conditioning Water for Steam Generation, A.S.M.E. Annual Meeting. By R. E. Hall.....	Dec. 1943 33
An Example of War-Time Expediency in Boiler Plant Layout.....	Oct. 1943 44
Annual Water Conference.....	Nov. 1943 52
A Useful Graph of the Properties of Steam-Water Mixtures.....	Sept. 1943 44
Causes and Prevention of Boiler Priming and Solids Carryover, Midwest Power Conference. By W. H. Rowand.....	May 1944 29
Chemical De-scaling of Boilers and Power Plant Equipment. By M. M. De Witt.....	Oct. 1943 41
Collection and Disposal of Fly Ash from Spreader Stokers. By K. H. Bowman.....	Sept. 1943 37
Combustion Gas Turbine, The. By F. K. Fischer and C. A. Meyer.....	May 1944 32
Combustion of Barley Size Anthracite, The, A.S.M.E. Annual Meeting. By Allen J. Johnson.....	Dec. 1943 34

	PAGE
Control Equipment for Single-Retort Underfeed Stokers. By H. G. Meissner.....	Mar. 1944 32
Corrosion as a Factor in Piping Maintenance, Midwest Power Conference. By L. G. Vande Bogart.....	May 1944 30
Corrosion by Hot Gases. By Richard C. Corey.....	Nov. 1943 34
Corrosion by Liquids. By Richard C. Corey.....	Aug. 1943 35
Denies Intent to Nationalize Coal Industry.....	Aug. 1943 44
Design Data for Overfire Jets. By Richard B. Engdahl.....	Mar. 1944 47
Determination of Steam Purity by the Electrical Conductivity.....	Oct. 1943 47
Dust Collectors Constructed of Non-Critical Materials. By Louis C. Whiton.....	Dec. 1943 49
Electric Utilities Meet War Demands Despite Added Burdens.....	July 1943 33
Errors in Temperature Measurement by Radiometric Methods. By W. T. Reid and R. C. Corey.....	Feb. 1944 30
Exit the Conventional Water Tank.....	Sept. 1943 43
Experimental Studies of Boiler Scale at 800 Psi. By J. A. Holmes and C. Jacklin.....	Jan. 1944 35
Formation of Bonded Deposits on Economizer Tubes Explained.....	Mar. 1944 56
Fuel Conservation Program Aims to Save 29 Million Tons of Fuel.....	May 1944 51
Fuel Problems in Brazil and Argentina. By J. B. Crane.....	July 1943 23
Fuels and Fuel Research in Great Britain, A.S.M.E. Annual Meeting. By W. C. Schroeder.....	Dec. 1943 35
Government Forewarns on Fuel Deliveries.....	July 1943 40
Heat Rates for Theoretical Regenerative Steam Cycle, A.S.M.E. Annual Meeting. By A. M. Selvey and P. H. Knowlton.....	Dec. 1943 34
High-Pressure and High-Temperature Steam for Marine Use. By W. H. Armacost.....	June 1944 48
High-Pressure Steam for Marine Propulsion. By R. H. Tingey	
Part I.....	Jan. 1944 41
Part II.....	Feb. 1944 47
Industrial Power Requirements.....	June 1944 52
Inertia Effect of Variable-Speed Control of Induced-Draft Fan Wheels. By Murray S. Kice.....	June 1944 38
Influence of Storage Upon Lignite Size Degradation. By C. J. Eckhardt, Jr. and C. W. Yates.....	July 1943 35
Interpretation of Analyses and Problems Encountered in Water Deposits. By J. A. Holmes and A. O. Walker.....	July 1943 30
Joint A.S.M.E.-A.I.M.E. Fuels Meeting Considers Research and Post War.....	Nov. 1943 40
Maintaining Compressors at Peak Operating Capacity. By B. Thiel.....	Jan. 1944 53
Maintenance Systems, Midwest Power Conference. By William A. Perry.....	May 1944 30
Manpower and Production.....	Sept. 1944 41
Methods of Inspection of Pressure Vessels and Piping. By W. D. Halsev.....	Nov. 1943 45
Midwest Power Conference—Post-War Planning of the Nation's Power Supply, Necessity for Research on Combustion Rates and Ash Behavior, Progress Toward Standardization of Turbine-Generators for Central Station Service, Causes and Prevention of Boiler Priming and Solids Carryover, Maintenance Systems, Corrosion as a Factor in Piping Maintenance.....	May 1944 28
Midwest Power Conference Scheduled for April 13-14.....	Feb. 1944 54
More About Marine Power Plants. By Alan J. Ruch.....	Nov. 1943 47
N.A.P.A. Standardizes Statistical Forms for Coal Users.....	Apr. 1944 40
Necessity for Research on Combustion Rates and Ash Behavior, Midwest Power Conference. By A. R. Mumford.....	May 1944 29
Necessity for Research on Combustion Rates and Ash Behavior. By A. R. Mumford.....	June 1944 43
New Combustion-Control Methods for All Standard Fuels, A.S.M.E. Annual Meeting. By Robert Reed.....	Dec. 1943 34
New Power for Old Boston. By G. A. Orrok, Jr. and W. P. Saunier.....	Apr. 1944 32
1944 Coal Outlook.....	Mar. 1944 55
Oblique Radiation on Boiler Tubes, A.S.M.E. Spring Meeting at Birmingham. By Lt. Commdr. W. S. Kimball.....	Apr. 1944 46
Operation of Hydro and Steam Capacity, A.S.M.E. Spring Meeting at Birmingham. By G. W. Spaulding.....	Apr. 1944 47
Operation of Steam Plants in Combined Steam and Hydro System. By A. T. Hutchins and Howard Durvea.....	Apr. 1944 42
Port Washington Second Unit in Operation.....	Jan. 1944 30
Post-War Planning of the Nation's Power Supply, Midwest Power Conference. By A. D. Bailey.....	May 1944 28
Power Supply at Synthetic Rubber Plant.....	Feb. 1944 28
Power Trains for Use Abroad.....	Dec. 1943 55
Power Trains to Serve Military Needs in Devastated Regions.....	June 1944 41
Program of A.S.M.E. Sixty-Fourth Annual Meeting.....	Nov. 1943 51
Progress Toward Standardization of Turbine-Generators for Central Station Service, Midwest Power Conference. By M. S. Oldacre.....	May 1944 29

	PAGE
Pulverizer Maintenance, A.S.M.E. Spring Meeting at Birmingham.....	Apr. 1944 46
Quick Starting of High-Pressure Turbines.....	July 1943 37
Separation and Transportation of Coal Dust as Pulverized Fuel. By H. C. Ray.....	Aug. 1943 42
Soot-Blower Applications.....	Mar. 1944 52
Steam Power and Fuel Problems Predominant at A.S.M.E. Annual Meeting—Furnace Performance Factors, Performance at Twin Branch, Experiences at Chicago Stations, Boilers on Public Service System, Detroit Units Compared, Units in Three Philadelphia Stations, Heat Transfer Measurements, Measurements on Oil-Fired Unit, Flow Characteristics of Coal-Ash Slags, High-Temperature Steam Corrosion, Potassium Salts Replacing Sodium Salts in Boiler-Water Conditioning, Heat Rates for Theoretical Regenerative Steam Cycle, Combustion-Control Methods, Burning Barley Size Anthracite, Fuels and Fuel Research in Great Britain, Uses for Fly Ash, Boiler Fan Selection and Use, Notch-Toughness Tests of Carbon-Molybdenum Pipe, Combustion in High-Pressure Chambers.....	Dec. 1943 28
Stoker Fuel-Bed Studies, A.S.M.E. Spring Meeting at Birmingham. Otto de Lorenzi.....	Apr. 1944 46
Topping Program at Sherman Creek Part I—Steam Generation. By R. T. Roberts.....	Aug. 1943 28
Part II—Turbine-Generator and Auxiliaries. By H. Knecht.....	Sept. 1943 28
Unit Power Plants for China.....	Feb. 1944 53
What Does 1944 Hold for Business? By W. L. Batt.....	Jan. 1944 51
AUTHORS—	
Allardice, T. B. and W. H. Rowand—Natural Circulation Test Results in the 2500-psi Twin Branch Boiler, A.S.M.E. Annual Meeting.....	Dec. 1943 28
Armacost, W. H.—High-Pressure and High-Temperature Steam for Manual Use.....	June 1944 48
Bailey, A. D.—Post-War Planning of the Nation's Power Supply, Midwest Power Conference.....	May 1944 28
Bailey, E. G. and Philip Sporn—Operating History of the 2500-psi Twin Branch Plant, A.S.M.E. Annual Meeting.....	Dec. 1943 28
Batt, W. L.—What Does 1944 Hold for Business?.....	Jan. 1944 51
Blizard, John—Absorption of Heat by the Walls of a Furnace, A.S.M.E. Annual Meeting.....	Dec. 1943 31
Bogart, L. G. Vande—Corrosion as a Factor in Piping Maintenance, Midwest Power Conference.....	May 1944 30
Bowman, K. H.—Collection and Disposal of Fly Ash from Spreader Stokers.....	Sept. 1943 37
Brandon, R. J. and W. A. Carter—Performance of Boilers 12 and 14 at the Trenton Channel Plant and Boilers 9 and 10 at the Marysville Plant of The Detroit Edison Company, A.S.M.E. Annual Meeting.....	Dec. 1943 30
Carter, W. A., and R. J. Brandon—Performance of Boilers 12 and 14 at the Trenton Channel Plant and Boilers 9 and 10 at the Marysville Plant of The Detroit Edison Company, A.S.M.E. Annual Meeting.....	Dec. 1943 30
Cohen, P. and W. T. Reid—The Flow Characteristics of Coal-Ash Slags in the Solidification Range, A.S.M.E. Annual Meeting.....	Dec. 1943 31
Corey, Richard C.—Corrosion by Liquids.....	Aug. 1943 35
Corrosion by Hot Gases.....	Nov. 1943 34
Corey, Richard C. and W. T. Reid—Errors in Temperature Measurement by Radiometric Methods.....	Feb. 1944 30
Crane, J. B.—Fuel Problems in Brazil and Argentina.....	July 1943 28
De Witt, M. M.—Chemical De-scaling of Boilers and Power Plant Equipment.....	Oct. 1943 41
Duryea, Howard and A. T. Hutchins—Operation of Steam Plants in Combined Steam and Hydro System.....	Apr. 1944 42
Eckhardt, Carl J., Jr. and C. W. Yates—Influence of Storage Upon Lignite Size Degradation.....	July 1943 35
Ely, F. G. and L. B. Schueler—Distribution of Heat Adsorption and Factors Affecting the Performance of the Twin Branch 2500-psi, 940-F Boiler with Reheat to 900 F, A.S.M.E. Annual Meeting.....	Dec. 1943 28
Engdahl, Richard B.—Design Data for Overfire Jets.....	Mar. 1944 47
Fischer, E. K. and C. A. Meyer—The Combustion Gas Turbine.....	May 1944 32
Hall, R. E.—A New Approach to the Problem of Conditioning Water for Steam Generation, A.S.M.E. Annual Meeting.....	Dec. 1943 33
Halsey, W. D.—Methods of Inspection for Pressure Vessels and Piping.....	Nov. 1943 45
Harlow, J. H.—Performance of Pulverized-Coal-Fired Boilers on the Philadelphia Electric Company System, A.S.M.E. Annual Meeting.....	Dec. 1943 30
Holmes, J. A. and A. O. Walker—Interpretation of Analyses and Problems Encountered in Water Deposits.....	July 1943 30
Holmes, J. A. and C. Jacklin—Experimental Studies of Boiler Scale at 800 Psi.....	Jan. 1944 35
Hutchins, A. T. and Howard Duryea—Operation of Steam Plants in Combined Steam and Hydro System.....	Apr. 1944 42
Jacklin, C. and J. A. Holmes—Experimental Studies of Boiler Scale at 800 Psi.....	Jan. 1944 35
Johnson, Allen J.—The Combustion of Barley Size Anthracite, A.S.M.E. Annual Meeting.....	Dec. 1943 34

	PAGE
Kice, Murray S.—Inertia Effect of Variable-Speed Control of Induced-Draft Fan Wheels.....	June 1944 38
Knecht, H.—Topping Program at Sherman Creek, Part II—Turbine-Generator and Auxiliaries.....	Sept. 1943 28
Knowlton, P. H. and A. M. Selvey—Heat Rates for Theoretical Regenerative Steam Cycle, A.S.M.E. Annual Meeting.....	Dec. 1943 34
Kreisinger, Henry and R. C. Patterson—Heat Transfer to Water-Cooled Furnace Walls, A.S.M.E. Annual Meeting.....	Dec. 1943 31
Macomber, H. E.—Addition to Capacity and Modernization of the Marysville Power House Part I.....	Oct. 1943 30
Part II.....	Dec. 1943 37
Part III.....	Feb. 1944 35
Part IV.....	Mar. 1944 39
Part V.....	May 1944 39
Meissner, H. G.—Control Equipment for Single-Retort Underfeed Stokers.....	Mar. 1944 32
Meyer, C. A. and E. K. Fischer—The Combustion Gas Turbine.....	May 1944 32
Michel, J. R.—Furnace Design and Development of Steam-Generating Units Burning Central Illinois Coal, A.S.M.E. Annual Meeting.....	Dec. 1943 29
Mumford, A. R.—Necessity for Research on Combustion Rates and Ash Behavior, Midwest Power Conference.....	May 1944 29
Necessity for Research on Combustion Rates and Ash Behavior.....	June 1944 43
Oldacre, M. S.—Progress Toward Standardization of Turbine-Generators for Central Station Service, Midwest Power Conference.....	May 1944 29
Orrok, George A., Jr. and W. P. Saunier—New Power for Old Boston.....	Apr. 1944 32
Patterson, R. C. and Henry Kreisinger—Heat Transfer to Water-Cooled Furnace Walls, A.S.M.E. Annual Meeting.....	Dec. 1943 31
Perry, William A.—Maintenance Systems, Midwest Power Conference.....	May 1944 30
Ray, H. C.—Separation and Transportation of Coal Dust as Pulverized Fuel.....	Aug. 1943 42
Reed, Robert—New Combustion-Control Methods for All Standard Fuels, A.S.M.E. Annual Meeting.....	Dec. 1943 34
Reid, W. T. and P. Cohen—The Flow Characteristics of Coal-Ash Slags in the Solidification Range, A.S.M.E. Annual Meeting.....	Dec. 1943 31
Reid, W. T. and R. C. Corey—Errors in Temperature Measurement by Radiometric Methods.....	Feb. 1944 30
Roberts, R. T.—Topping Program at Sherman Creek, Part I—Steam Generation.....	Aug. 1943 28
Rowand, W. H.—Causes and Prevention of Boiler Priming and Solids Carryover, Midwest Power Conference.....	May 1944 29
Rowand, W. H. and T. B. Allardice—Natural Circulation Test Results in the 2500-psi Twin Branch Boiler, A.S.M.E. Annual Meeting.....	Dec. 1943 28
Ruch, Alan—More About Marine Power Plants.....	Nov. 1943 47
Saunier, W. P. and George A. Orrok, Jr.—New Power for Old Boston.....	Apr. 1944 32
Schroeder, W. C.—Fuels and Fuel Research in Great Britain, A.S.M.E. Annual Meeting.....	Dec. 1943 35
Schueler, L. B. and E. G. Ely—Distribution of Heat Adsorption and Factors Affecting the Performance of the Twin Branch 2500-psi, 940-F Boiler with Reheat to 900 F, A.S.M.E. Annual Meeting.....	Dec. 1943 28
Selvey, A. M. and P. H. Knowlton—Heat Rates for Theoretical Regenerative Steam Cycle, A.S.M.E. Annual Meeting.....	Dec. 1943 34
Sporn, Philip and E. G. Bailey—Operating History of the 2500-psi Twin Branch Plant, A.S.M.E. Annual Meeting.....	Dec. 1943 28
Thiel, B.—Maintaining Compressors at Peak Operating Capacity.....	Jan. 1944 53
Tingey, R. H.—High-Pressure Steam for Marine Propulsion Part I.....	Jan. 1944 41
Part II.....	Feb. 1944 47
Walker, A. O. and J. A. Holmes—Interpretation of Analyses and Problems Encountered in Water Deposits.....	July 1943 30
Weinheimer, C. M.—An Evaluation of the Importance of Physical and Chemical Properties of Fly Ash in Creating Commercial Outlets for the Material, A.S.M.E. Annual Meeting.....	Dec. 1943 35
Weisberg, Herman—Pulverized-Coal-Fired Boiler Furnaces, A.S.M.E. Annual Meeting.....	Dec. 1943 29
Whiton, Louis C.—Dust Collectors Constructed of Non-Critical Materials.....	Dec. 1943 49

REVIEW OF NEW BOOKS—

A.S.T.M. Specifications for Steel Piping Materials. Issued by the American Society for Testing Materials.	May 1944 53
Fundamentals of Coal Sampling (Bureau of Mines Bulletin No. 454). By Bertrand A. Landry.....	May 1944 53
Graphical Solutions (Second Edition). By Charles O. Mackey.....	Apr. 1944 54
Guide to Weldability of Steels. American Welding Society.....	May 1944 53
Heating, Ventilating and Air Conditioning Guide—1944. Issued by the American Society of Heating and Ventilating Engineers.....	May 1944 53

	PAGE
How to Maintain Electric Equipment in Industry. Issued by General Electric Company.....	Oct. 1943 51
Index to A.S.T.M. Standards and Tentative Standards.....	Apr. 1944 54
MacQuown's Coal Directory and Buyers Guide. Edited by M. C. MacQuown.....	May 1944 53
Manual of A.S.T.M. Standards on Refractory Materials. Compiled by the American Society for Testing Materials.....	Oct. 1943 51
1943 Wage and Hour Manual.....	May 1943 53
Oxy-Acetylene Handbook, The. Issued by the Linde Air Products Company.....	May 1944 53
Patent Law. By Chester H. Biesterfeld.....	Oct. 1943 51
Practical Design of Welded Steel Structures, The. By H. Malcolm Priest.....	Apr. 1944 54
Principles and Practice of Flow Meter Engineering. By L. K. Spink.....	May 1944 53
Proceedings of the 4th Annual Water Conference of the Engineers Society of Western Pennsylvania.....	Apr. 1944 54
Proceedings of the 37th Annual Meeting of the Smoke Prevention Association of America.....	Oct. 1943 51
Questions and Answers for Marine Engineers—Boilers and Engines. Compiled by Captain H. C. Dinger, U.S.N. (Retired).....	May 1944 53
Steam Boiler Yearbook and Manual, The. Edited by Sidney D. Scorer.....	Oct. 1943 51
X-Rays in Research and Industry. By H. Hirst.....	Oct. 1943 51

CLASSIFIED INDEX—

Auxiliaries

Addition to Capacity and Modernization of Marysville Power House, <i>Part IV</i> . By H. E. Macomber.....	Mar. 1944 39
Control Equipment for Single-Retort Underfeed Stokers. By H. G. Meissner.....	Mar. 1944 32
Maintaining Compressors at Peak Operating Capacity. By Bruno Thiel.....	Jan. 1944 53
Topping Program at Sherman Creek, <i>Part II—Turbine-Generator and Auxiliaries</i>	Sept. 1943 28

Boilers

Chemical De-scaling of Boiler and Power Plant Equipment. By M. M. De Witt.....	Oct. 1943 41
Determination of Steam Purity by the Electrical Conductivity.....	Oct. 1943 47
An Example of War-Time Expediency in Boiler Plant Layout.....	Oct. 1943 44
Methods of Inspection for Pressure Vessels and Piping. By W. D. Halsey.....	Nov. 1943 45
More About Marine Power Plants. By Alan J. Ruch.....	Nov. 1943 47
Soot-Blower Applications.....	Mar. 1944 52
Topping Program at Sherman Creek, <i>Part I—Steam Generation</i> . By R. T. Roberts.....	Aug. 1943 28

Chimneys

Collection and Disposal of Fly Ash from Spreader Stokers. By K. H. Bowman.....	Sept. 1943 37
Dust Collectors Constructed of Non-Critical Materials. By Louis C. Whiton.....	Dec. 1943 49

Coals

Burning Mixtures of Bituminous Coal and Anthracite Fines. Editorial.....	Mar. 1944 31
Coal Regulations Predicated on Stock Piles.....	Dec. 1943 55
Denies Intent to Nationalize Coal Industry.....	Aug. 1943 44
1944 Coal Outlook, The.....	Mar. 1944 55

Coal and Ash Handling Systems

Addition to Capacity and Modernization of Marysville Power House, <i>Part III</i> . By H. E. Macomber.....	Feb. 1944 35
--	--------------

Feedwater

Corrosion by Liquids. By R. C. Corey.....	Aug. 1943 35
Experimental Studies of Boiler Scale at 800 Psi. By J. A. Holmes and C. Jacklin.....	Jan. 1944 35
Interpretation of Analyses and Problems Encountered in Water Deposits.....	July 1943 30

Flue Gases

Corrosion by Hot Gases. By Richard C. Corey.....	Nov. 1943 34
--	--------------

COMBUSTION—June 1944

Fuels

Fuel Conservation Program Aims to Save 29 Million Tons of Fuel.....	May 1944 51
Fuel Problems in Brazil and Argentina. By J. B. Crane.....	July 1943 28
Government Forewarns on Fuel Deliveries.....	July 1943 40
Influence of Storage Upon Lignite Size Degradation.....	July 1943 35
Joint A.S.M.E.-A.I.M.E. Fuels Meeting Considers Research and Post War.....	Nov. 1943 40
Limited Rationing of Bituminous Coal. Editorial.....	Sept. 1943 27
N.A.P.A. Standardizes Statistical Forms for Coal Buyers.....	Apr. 1944 40
Separation and Transportation of Coal Dust as Pulverized Fuel. By R. C. Ray.....	Aug. 1943 42

General Practice, Developments and Trends

British Power Station Performances.....	May 1944 57
---	-------------

Heat Recovery

Formation of Bonded Deposits on Economiser Tubes Explained.....	Mar. 1944 56
---	--------------

Installations

Addition to Capacity and Modernization of the Marysville Power House. By H. E. Macomber	
<i>Part I</i>	Oct. 1943 30
<i>Part II</i>	Dec. 1943 37
<i>Part III</i>	Feb. 1944 35
<i>Part IV</i>	Mar. 1944 39
<i>Part V</i>	May 1944 39
New Power for Old Boston. By G. A. Orrok, Jr. and W. P. Saunier.....	Apr. 1944 32
Operation of Steam Plants in Combined Steam and Hydro System. By A. T. Hutchins and Howard Duryea.....	Apr. 1944 42
Port Washington Second Unit in Operation.....	Jan. 1944 30
Power Supply at Synthetic Rubber Plant.....	Feb. 1944 28
Topping Program at Sherman Creek	
<i>Part I—Steam Generation</i> . By R. T. Roberts.....	Aug. 1943 28
<i>Part II—Turbine-Generator and Auxiliaries</i> . By H. Knecht.....	Sept. 1943 28

Marine Practice

High-Pressure Steam for Marine Propulsion. By R. H. Tingey	
<i>Part I</i>	Jan. 1944 41
<i>Part II</i>	Feb. 1944 47
Marine Engineers. Editorial.....	Sept. 1943 27
More About Marine Power Plants. By Alan J. Ruch.....	Nov. 1943 47

Research

Dust Collectors Constructed of Non-Critical Materials. By Louis C. Whiton.....	Dec. 1943 49
Experimental Studies of Boiler Scale at 800 Psi. By J. A. Holmes and C. Jacklin.....	Jan. 1944 35
Necessity for Research on Combustion Rates and Ash Behavior. By A. R. Mumford.....	June 1944 43

Turbine-Generators

Addition to Capacity and Modernization of Marysville Power House, <i>Part III</i> . By H. E. Macomber.....	Feb. 1944 35
Combustion Gas Turbine, The. By F. K. Fischer and C. A. Meyer.....	May 1944 32
Quick Starting of High-Pressure Turbines.....	July 1943 37
Topping Program at Sherman Creek, <i>Part II—Turbine-Generator and Auxiliaries</i> . By H. Knecht.....	Sept. 1943 28

Smoke Abatement

Watch the Smoke. Editorial.....	Apr. 1944 31
---------------------------------	--------------

Steam Pressures, Temperatures and Cycles

Determination of Steam Purity by the Electrical Conductivity.....	Oct. 1943 47
Errors in Temperature Measurement by Radiometric Methods. By W. T. Reid and R. C. Corey.....	Feb. 1944 30
Experimental Studies of Boiler Scale at 800 Psi. By J. A. Holmes and C. Jacklin.....	Jan. 1944 35
High-Pressure and High-Temperature Steam for Marine Use. By W. H. Armacost.....	June 1944 48
High-Pressure Steam for Marine Propulsion. By R. H. Tingey	
<i>Part I</i>	Jan. 1944 41
<i>Part II</i>	Feb. 1944 47
Quick Starting of High-Pressure Turbines.....	July 1943 37

Topping Program at Sherman Creek	
Part I—Steam Generation. By R. T. Roberts.....	Aug. 1943 28
Part II—Turbine-Generator and Auxiliaries. By H. Knecht.....	Sept. 1943 28
A Useful Graph of the Properties of Steam-Water Mixtures.....	Sept. 1943 44

Stokers

Addition to Capacity and Modernization of Marysville Power House—Part V. By H. E. Macomber.....	May 1944 39
Collection and Disposal of Fly Ash from Spreader Stokers. By K. H. Bowman.....	Sept. 1943 37
Control Equipment for Single-Retort Underfeed Stokers. By H. G. Meissner.....	Mar. 1944 32
Design Data for Overfire Jets. By Richard B. Engdahl.....	Mar. 1944 47

Miscellaneous


A.S.M.E. Annual Meeting, Steam Power and Fuel Problems Predominate.....	Dec. 1943 28
A.S.M.E. Spring Meeting at Birmingham.....	Apr. 1944 46
Annual Water Conference.....	Nov. 1943 52
Chemical De-scaling of Boiler and Power Plant Equipment. By M. M. De Witt.....	Oct. 1943 41
Corrosion by Hot Gases. By Richard C. Corey.....	Nov. 1943 34
Electric Utilities Meet War Demands Despite Added Burdens. By C. W. Kellogg.....	July 1943 33
Exit the Conventional Water Tank.....	Sept. 1943 43
Industrial Power Requirements.....	June 1944 52
Inertia Effect of Variable-Speed Control of Induced-Draft Fan Wheels. By Murray S. Kice.....	June 1944 38
Joint A.S.M.E.-A.I.M.E. Fuels Meeting Considers Research and Post War.....	Nov. 1943 40
Manpower and Production.....	Sept. 1943 41
Midwest Power Conference.....	May 1944 28
Midwest Power Conference Scheduled for April 13-14.....	Feb. 1944 54
N.A.P.A. Standardizes Statistical Forms for Coal Buyers.....	Apr. 1944 40
Operation of Steam Plants in Combined Steam and Hydro System. By A. T. Hutchins and Howard Duryea.....	Apr. 1944 42
Power Trains for Use Abroad.....	Dec. 1943 55
Power Trains to Serve Military Needs in Devastated Regions Abroad.....	June 1944 41
Program of A.S.M.E. Sixty-Fourth Annual Meeting.....	Nov. 1943 51
Steam Power and Fuel Problems Predominant at A.S.M.E. Annual Meeting.....	Dec. 1943 28
What Does 1944 Hold for Business? By W. L. Batt.....	Jan. 1944 51

ADVERTISERS IN THIS ISSUE

Air Preheater Corporation, The.....	17
American Blower Corporation.....	28 and 29
Bailey Meter Company.....	10 and 11
C. O. Bartlett & Snow Company, The.....	15
Bayer Company, The.....	6
Beaumont Birch Company.....	55
Buell Engineering Company, Inc.....	36
Philip Carey Mfg. Company, The.....	51
Clarage Fan Company.....	4
Coal Bureau, Upper Monongahela Valley Association.....	27
Cochrane Corporation.....	47
Combustion Engineering Company, Inc.....	Second Cover, 8 and 9
Crosby Steam Gate & Valve Company.....	35
Dampney Company of America, The.....	33
Davis Regulator Company.....	60
De Laval Steam Turbine Company.....	46
Dowell Incorporated.....	23
Diamond Power Specialty Corporation.....	Third Cover
Edward Valve & Mfg. Company, Inc., The.....	5
Elliott Company.....	19
Engineer Company, The.....	56
General Coal Company.....	54
A. P. Green Fire Brick Company.....	25
Hagan Corporation.....	20 and 21
Hall Laboratories, Inc.....	20 and 21
Joshua Hendy Iron Works.....	26
Infilco Incorporated.....	24
Johns-Manville.....	16
Midwest Piping & Supply Company, Inc.....	12
Northern Equipment Company.....	2
Plibrico Jointless Firebrick Company.....	7
Poole Foundry & Machine Company.....	54
Wm. Powell Company, The.....	22
Pratt-Daniel Corporation.....	3
Reliance Gauge Column Company, The.....	42
Research Corporation.....	18
Sauerman Bros., Inc.....	53
Steel & Tubes Division, Republic Steel Corporation.....	30 and 31
Stock Engineering Company.....	55
Terry Steam Turbine Company, The.....	32
Union Asbestos and Rubber Company.....	Fourth Cover
Vulcan Soot Blower Corporation.....	13
Yarnall-Waring Company.....	14

A VALVE THAT WILL INTEREST EVERY POWER ENGINEER

THE DAVIS No. 265 HIGH PRESSURE RELIEF VALVE



for:

- Turbine relief on bleeder system.
- Protection of any boiler room or process equipment by relief to atmosphere.
- Relief of high pressure lines to low pressure lines at predetermined pressure.
- Plants carrying multiple boiler pressures to protect lower pressure systems.

The Davis No. [265 High Pressure Relief Valve, an exclusive Davis design offers numerous features of advantage:

1. Multiple springs—less spring accumulation—less buildup for maximum relief—less blowdown to close.
2. Requires appreciably less head room because of compact design with springs located at sides.
3. Center adjusting screw provides quick, easy change of pressure setting.
4. Can be supplied with test lever.
5. Available with hold open device.
6. Available in semi-steel or steel with bronze or stainless steel trim.
7. Size range 4" to 30".

DAVIS REGULATOR COMPANY

2510 S. Washtenaw Ave.

Chicago, Ill.



DAVIS REGULATOR CO.



These Fan Stacks are evacuating dangerous gases to atmosphere. Their construction, when driven by weather-proof motors, eliminates the necessity of housing.

When you install a Thermix Fan-Stack you not only save steel vitally needed for the war, but also save money.

No connecting breeching is required between the fan and chimney as with an ordinary fan and stack—no complicated ducts are needed as with a double inlet fan. Thermix Stacks are of smaller average diameter than a cylindrical stack or chimney, and only one support (instead of separate supports) is needed for the Thermix Fan and Stack combined. Consequently, they cost less for material and less for labor.

The Thermix is a combination of a fan and a stack in one unit which operates as a single unit. Because it is designed and built by a single, responsible manufacturer, you are assured complete coordination of the mechanical-draft stack, the inlet-breeching and the fan itself.

Our Catalog No. 109 gives full particulars. Write for a copy.


PRAT-DANIEL CORPORATION, Port Chester, N. Y.

Also manufacturers of non-priority dust collectors

Project and Sales Engineers

THERMIX ENGINEERING CO., Greenwich, Conn.


Representatives in Principal Cities



THERMIX FAN STACK

Another Reason Why

CLARAGE is Ace-High
in this Toughest
of ALL
Fan Services



A—Water Inlets. B—Water Outlets.
C—Oil Rings. D—Thrust Collars (forged,
turned and ground); Integral part of shaft.
E—Seals prevent dust leakage into bearing.

BETTER BEARINGS GUARD Against Operating Failures on Vital War-Time Jobs!


Wheel tip speeds may run as high as 4 miles per minute—temperatures may exceed 700° F.—that's modern induced draft—*toughest of all fan services!*

To meet such requirements successfully, Clarage Type RT Fans have water-cooled bearings of liberal size, as shown above. Note high grade construction and precision features.


Note, too, that cooling water is circulated through each half of the bearing sleeve independently of the other—no joints or gaskets—no possibility of water leaking into bearing lubrication.

These BETTER bearings are an important factor in assuring each Clarage RT Induced Draft Fan a trouble-free service life far longer than normal expectancy.

And this ability to out-perform and out-last is equally characteristic of other Clarage Fans and Blowers. If you have ANY war-time air-handling problem, it will pay you to get in touch with us.



A—Water Inlets. B—Water Outlets.
C—Oil Filler Cup and Pipe. D—Bottom of
Bearing and top of Support machined for
accurate alignment. E—Shaft Seal prevents
escape of gases from fan.



RT Induced
Draft Fan serv-
icing public util-
ity—one of over
2,000 Clarage
power plant in-
stallations.
Water-cooled
bearings in fore-
ground—big
hunky ones OK
for any oper-
ating condition.



**COMPLETE
AIR CONDITIONING**
•
COOLING
•
VENTILATION
•
FACTORY HEATING
•
MECHANICAL DRAFT
•
FANS and BLOWERS
for
INDUSTRIAL NEEDS

Clarage Fan Company Kalamazoo, Mich.


APPLICATION ENGINEERING OFFICES IN ALL PRINCIPAL CITIES

Edward

GAGE VALVES

FOR services where bar stock valves are often used—gage, meter, dead end and instrument lines, pump vents and Diesel and gas engines—Edward Fig. 152 gage valves have the advantage of much greater strength.

Because they are drop forged steel, the bodies of Edward gage valves have sounder structure and greater strength than bodies machined from a bar. For non-shock service up to 4000 lb at 150 F and in steam service up to 600 lb at 750 F. Made to customary Edward precision and quality standards, yet remarkably low in price because of production runs.



DESIGN DETAILS

Rugged, functional design qualifies Edward Fig. 152 gage valves for long life in tough service. Notice exclusive safety taper threaded bonnet joint, EValloy stainless steel stem with semi-needle disk, knobbed handwheel for easy grip and leverage, back seating shoulder to prevent backing stem out of bonnet and to permit re-packing under pressure. Bonnets and packing nuts are EValized to cut corrosion and wear.

DIMENSIONS AND RATINGS

4000 lb at 150 F

600 lb at 750 F

475 lb at 1000 F

DIMENSIONAL DETAILS

SIZE	1/8"	1/4"	3/8"	1/2"
End to end—Globe	1 13/16	1 13/16	2 1/4	2 3/4
Center to end—Angle	29/32	29/32	1 1/8	1 3/8
Center to top—Open	3 5/8	3 5/8	3 7/8	4
Port diameter	1/8	3/16	1/4	3/8
Weight—lb	1	1	1 1/4	1 1/2

For illustrations, dimensions and descriptions of the Edward line of cast and forged steel valves write for a free copy of the new Edward BETTER VALVES Catalog No. 102.

THE EDWARD VALVE & MFG. CO., INC., • EAST CHICAGO, INDIANA

EDWARD *Steel* VALVES



HOW TO JUDGE A SOOT CLEANER


There are two characteristics you should insist on in any soot cleaner you are asked to buy:

1. Make sure that the soot cleaner you are offered will operate efficiently at all stages of the cleaning operation—especially in the beginning of the cleaning arc.

(**BAYER SOOT CLEANERS** do operate efficiently at all stages including the beginning of the cleaning arc because their "balanced valved" design promptly provides an ample flow of steam at the very outset of the cleaning operation and throughout the cleaning arc.)

2. Make sure that the soot cleaner you are offered is of such design and construction that it will function efficiently for a very long time with very little attention. In this connection it will pay you to be particularly inquisitive regarding valve and stuffing box troubles and maintenance.

(**BAYER SOOT CLEANERS** require very little attention. Because of their "balanced valved" design the valve always closes gently; consequently the valve seat surfaces remain in good condition a very long time. And, because there is no strain on the moving element, the stuffing box remains tight a very long time. So that very little maintenance is needed.)



Consider the above facts. Then inquire among the thousands of Bayer Soot Cleaner users. Your conclusion will be:

**BUY BAYER BALANCED VALVED SOOT
CLEANER**

for highest first and final value!

the BAYER company

ST. LOUIS, MISSOURI, U. S. A.

Tailor-made

TO SUIT YOUR PARTICULAR CONDITIONS

Every installation of Beco-Turner baffles is a "tailor-made" job, designed by our baffle engineers to conform to the requirements of your boiler and fuel-burning equipment and to deliver highest efficiency and capacity under your particular operating conditions.

Beco-Turner designs are not limited to standard shapes as are tile and flame-plate baffles, but may be installed to any design which will produce the best performance. For this reason, the installation of Beco-Turner baffles results in such improvements as shown in the two prints opposite.

But good baffles are a matter of construction as well as design, and here's where Beco-Turner scores again. Constructed of highest quality castable refractory material, Beco-Turner baffles are gas-tight as installed and remain gas-tight since Beco-Turner expansion joints prevent cracks and leaks by compensating for expansion and contraction.

Do you need more steam? Is your stack temperature too high? Are you bothered with slagging of tubes due to excessive gas velocity? Then it will pay you to investigate Beco-Turner service. Write for catalog covering Beco-Turner baffles and Plibrico monolithic settings. Or send blueprints showing your present or contemplated baffles for our recommendations. No obligation.


PLIBRICO JOINTLESS FIREBRICK CO.

1820 Kingsbury St. (Dept. F) Chicago 14, Ill.


BUILDERS OF

BECO-TURNER BAFFLES

COMBUSTION—June 1944



For straight tube boilers: An 800 hp. horizontal boiler at an Ohio central station as equipped with Beco-Turner baffles which replaced ordinary flame-plate baffles. Note the increased tube area in the first pass.



For bent tube boilers: A 600 hp. bent tube boiler at an Eastern aircraft manufacturing plant as equipped with Beco-Turner cross baffles which replaced original parallel baffles. The new baffles give more complete heat absorption due to more efficient cross flow of gases.

MEET THE MEN



WHO WANT

Partial list to date of Coordinators of the NATIONAL FUEL EFFICIENCY PROGRAM

ALABAMA

MR. JOHN M. GALLALEE
Head, Dept. of Mech. Eng.
University of Alabama
UNIVERSITY

MR. LOUIS GRABENSTEDER
Mechanical Engineer
313 Williams Street
HUNTSVILLE

CALIFORNIA

MR. GERALD E. CHESSE
Industrial Power Engineer
Pacific Gas & Electric Company
FRESNO

MR. R. L. HUMMER
Consulting Engineer
2201 Arrowhead Avenue
SAN BERNARDINO

COLORADO

MR. FRANK H. PROUTY
Prouty Bros., Engineering Co.
Exchange Building
DENVER

CONNECTICUT

MR. HENRI B. VAN ZELM
Consulting Engineer
11 Asylum Street
HARTFORD

DISTRICT OF COLUMBIA

MR. H. K. KUGEL
Chief Engineer
Smoke Regulation & Boiler Insp.
District Building
WASHINGTON

FLORIDA

MR. NORMAN C. ASCHER
Miami Builders Exchange Building
MIAMI

MR. CHARLES H. DENNISTON
Sales Manager
Florida Weathermakers, Inc.
805 Hogan Street
JACKSONVILLE

MR. G. P. PATTERSON
W. B. Haggerty, Inc.
805 Morgan Street
P. O. Box 2971
TAMPA 1

IDAHO

MR. O. E. STRAWN
Strawn and Company
824 Idaho Street
BOISE

ILLINOIS

MR. LYLE E. BOYD
A-C Supervisor
Caterpillar Military Engine Co.
Victory Ordnance Plant
DECATUR

MR. E. A. FIELD, JR.
Conco Engineering Works
MENDOTA

MR. W. D. LANGTRY
President
Commercial Testing & Eng. Co.
307 N. Michigan Ave.
CHICAGO 1

MR. EINAR WINHOLT
Supervising Power Engineer
Deere & Company
MOLINE

INDIANA

MR. CLAUDE WERTZ
Malay & Wertz Lumber Company
900 East Columbia Street
EVANSVILLE

IOWA

MR. JOHN M. DRABELLE
Consulting Engineer
Iowa Elec. Light & Power Co.
Security Building
CEDAR RAPIDS

MR. EUGENE O. OLSON

Professor
Iowa State College
804 Tenth Street
AMES

KANSAS

MR. LINN HELANDER
Head of Mech. Eng. Dept.
Kansas State College
MANHATTAN

MR. ALBERT L. MAILLARD
The Military Chemical Works, Inc.
P. O. Box 604
PITTSBURGH

MR. WILLIAM F. RYAN

Chief Engineer
The Salina Supply Company
302-304 North Santa Fe St.
SALINA

MR. P. W. THOMAS

President
Thomas, Stone & French, Inc.
204 North Waco Avenue
WICHITA 1

KENTUCKY

MR. C. S. CROUSE
Head, Dept. of Min. & Met. Eng.
University of Kentucky
LEXINGTON

LOUISIANA

MR. EDWIN L. DENNIS
Consulting Engineer
416 Louisiana National Bank
BATON ROUGE

MARYLAND

MR. JAMES H. McKAY
Smoke Control Engineer
City of Baltimore
BALTIMORE

MASSACHUSETTS

MR. DAVID A. CHAPMAN
Consultant
War Production Board
17 Court Street
BOSTON 2

MICHIGAN

MR. P. W. THOMPSON
Vice Pres. in Charge of Eng.
The Detroit Edison Company
2000 Second Avenue
DETROIT 26

MINNESOTA

MR. HENRY G. LYKKEN
Manager
Hurricane Pulverizer Co.
1611 Central Avenue
MINNEAPOLIS 12

MR. JOHN McCABE

Minnesota Power & Light Co.
30 West Superior Street
DULUTH

MISSISSIPPI

MR. B. Y. BUCKLEY
Superintendent
Greenwood Elec. Light & Water Pl't
GREENWOOD

MISSOURI

MR. SAM F. DALTON
c/o Dalton Coal & Material Co.
15 North Fourth Street
COLUMBIA

MR. MELVIN P. HATCHER
Director
Kansas City Water Dept.
KANSAS CITY

MR. RICHARD F. WOOD

Executive Director
Solid Fuel Institute
407 N. Eighth Street
ST. LOUIS

NEBRASKA

MR. C. W. BURDICK
Commissioner
City Water, Light & Ice Co.
GRAND ISLAND

MR. ANDREW S. REIFF
Superintendent
City of Hastings W. & L. Dept.
HASTINGS

MR. LARRY SHOMAKER

Supl. of Gas Sales
Northern Natural Gas Co.
Aquila Court Bldg.
OMAHA

MR. R. H. STEBBINGS
The Lincoln Tel. & Tel. Co.
LINCOLN

NEW JERSEY

MR. WILLIAM G. CHRISTY
Smoke Abatement Engineer
Dept. of Smoke Reg. of Hudson Co.
Court House
JERSEY CITY

NEW MEXICO

MR. HUGH MUNN
General Manager
Albuquerque Lumber Company
501 North First Street
ALBUQUERQUE

NORTH CAROLINA

MR. WILLIAM M. WALLACE II
Consulting Engineer
711 Corcoran Street
DURHAM

NORTH DAKOTA

MR. O. T. SOLBERG
Sales Manager
Knife River Coal Mining Co.
BISMARCK

NEW YORK

MR. EARL C. PAYNE
Consulting Engineer
Consolidation Coal Co.
20 Rockefeller Plaza
NEW YORK

OHIO

MR. JAMES H. HERRON
James H. Herron Eng. Co.
1360-1364 West Third Street
CLEVELAND

MR. CARL J. KIEFER
President
Schenley Distilleries, Inc.
26 East Sixth Street
CINCINNATI

MR. A. W. KIMMEL
Ready Mixed Corporation
20 Keewee Street
DAYTON

MR. HARRY E. NOLD
Director
Eng. Sci. & M'g'ment War Train.
Room 214, Lord Hall, Ohio State U.
COLUMBUS 10

OKLAHOMA

MR. FRED G. BECKMAN
Muskogee Iron Works
MUSKOGEE

MR. L. W. CRUMP
Industrial Sales Manager
Oklahoma Natural Gas Company
TULSA

MR. A. D. STODDARD
Vice-President
Halliburton Oil Well Cem. Co.
DUNCAN

PENNSYLVANIA

MR. MERRILL F. BLANKIN
1124 Spring Garden Street
PHILADELPHIA 23

MR. LAYTON A. CLUGH
204 East 22nd Ave.
ALTOONA

MR. HENRY F. HEBLEY
Director of Research
Pittsburgh Coal Company
P. O. Box 146
PITTSBURGH 30

SOUTH CAROLINA

MR. E. M. WILLIAMS
Fuel Engineer
Clinchfield Coal Co.
SPARTANBURG

SOUTH DAKOTA

MR. FRANK E. WYTENBACK
Business Manager
Aberdeen Public Schools
ABERDEEN

TENNESSEE


MR. JOHN CALLAN
Tennessee Eastman Corporation
KINGSPORT

MR. C. J. GASKELL
C. J. Gaskell Company
P. O. Box 162
MEMPHIS 1

MR. ROSCOE W. MORTON
Professor of Mechanical Eng.
The University of Tennessee
KNOXVILLE

TO HELP YOU SAVE FUEL!

HOW THE NATIONAL FUEL EFFICIENCY PROGRAM FUNCTIONS



TEXAS

MR. CARL J. ECKHARDT, JR.
Professor of Mechanical Engineering
The University of Texas
AUSTIN

MR. NAT W. HARDY
Architect and Consulting Engineer
1014 Nixon Building
CORPUS CHRISTI

MR. M. M. MASSEY
Master Mechanic
P. O. Box 2
KELLYS

MR. W. A. McDONALD
Superintendent Power Dept.
Houston Light. & Power Co.
HOUSTON 1

MR. FREDERICK W. RABE
Consulting Engineer
Continental Motors Corp.
3105 Cornell Ave.
DALLAS 5

MR. EDWIN SNOOK
Utilization Engineer
Amarillo Gas Company
AMARILLO

MR. RICHARD K. WERNER
Consulting Mechanical Engineer
W. T. Waggoner Building
FORT WORTH

VIRGINIA

MR. D. J. HOWE
Assistant to Coal Traffic Manager
Norfolk & Western Railway Co.
ROANOKE 17

MR. FRED O. SAUNDERS
State Mechanical Engineer
State Office Building
RICHMOND

WEST VIRGINIA

MR. HARRY S. SLOCUM
4 Whitethorne Land
BLUEFIELD

WISCONSIN

MR. GROVER KEETH
Chief Engineer
Marathon Paper Mills Company
ROTHSCHILD

MR. PARKER A. MOE
Chief Operating Engineer
International Harvester Co.
3713 West Bramling Lane
MILWAUKEE

MR. BURT A. POST
Manager
Post Power Supply Company
843 East North Street
APPLETON

MR. THOMAS J. WHALEN
Thomas J. Whalen Co.
91—8th Street
FOND DU LAC

WYOMING

MR. J. M. McINTIRE
Northern Utilities Company
CASPER


The calibre of these men — the Coordinators of the National Fuel Efficiency Council — speaks for the character of the program they have undertaken which is a drive by industry and for industry to help stretch the entirely inadequate fuel supply of America by promoting greater fuel efficiency and reducing heat losses.

Each of these coordinators will direct a group of regional engineers in his own locality — one of whom will visit your plant to enlist your cooperation. He will carry with him helpful information on fuel conservation which has been compiled by voluntary committees comprising the manufacturers of all classes of equipment used in the production and utilization of steam. All of these men are donating their services to help your country avert a disastrous fuel shortage.

If they succeed in attaining the first year's objective — the conservation of 29,000,000 tons of coal and proportionate amounts of gas and oil — they will help the country through the threatening winter of 1944-45 when fuel promises to be the most critical of all critical materials. If they succeed, they will avoid curtailment of war production and save industry from the threat of shortages that otherwise might require relief in some form of allocation.

And they will succeed if every man in industry who uses fuel recognizes the stark necessity of the situation in terms of the war effort abroad and civilian life at home — and lends his fullest cooperation. A-794

To obtain more details write the coordinator nearest you.



This space is contributed by the undersigned company for the purpose of furthering the important work of the National Fuel Efficiency Program.

COMBUSTION ENGINEERING



200 MADISON AVENUE

NEW YORK 16, N. Y.

C-E PRODUCTS INCLUDE ALL TYPES OF BOILERS, FURNACES, PULVERIZED FUEL SYSTEMS AND STOKERS; ALSO SUPERHEATERS, ECONOMIZERS AND AIR HEATERS

BAILEY BOILER METERS ENGINEERED

**Bailey Field Engineers backed
installations adjust each Bailey Boiler**

*The use of Bailey Boiler Meters and Bailey engineering
service for fuel conservation dates back through World War I.*



*Modern installations of Bailey Boiler Meters usually
include Bailey Boiler Control to automatically
maintain maximum fuel economy and other
desirable operating conditions.*

BAILEY METER CONTROL...

BOILER METERS • MULTI-POINTER GAGES • FLUID METERS • RECORDERS • SUPERHEAT

—YOUR PASSPORT to FUEL CONSERVATION

by the know-how gained from thousands of successful Steam Flow—Air Flow Meter to the particular requirements of the unit which it serves. The meter then serves as a guide to firemen in obtaining maximum fuel conservation in everyday operation.

Bailey engineering service starts with the selection of equipment and continues through the design, construction, calibration, installation and final adjustment on the job. Much of this engineering work is done in the user's plant by Bailey Field Engineers who have been thoroughly trained in combustion and automatic control practice. These engineers are stationed in over 30 industrial areas throughout the United States and Canada for the purpose of rendering prompt "on the spot" engineering service without undue traveling expense.

The Bailey Engineer in your community has "know-how" at his command which was developed by over 25 years experience with the Steam Flow—Air Flow method of combustion control. This includes the records of tests on thousands of boiler installations covering a wide range of fuels, furnaces and fuel burning equipment. You will find that this engineer has more to offer than meters and controllers. He is primarily interested in helping you to secure maximum fuel conservation and other benefits which result from the intelligent use of correctly selected and properly applied instrumentation.

G-21

BAILEY METER COMPANY

1025 IVANHOE ROAD • CLEVELAND 10, OHIO

Bailey Meter Company Limited, Montreal, Canada

The Complete Combustion Control System

CONTROL • DESUPERHEAT CONTROL • COMBUSTION CONTROL • FEED WATER CONTROL

THE Preferred FLANGED JOINT FOR WELDED PIPING SYSTEMS

MIDWEST LAP-JOINT STUB ENDS

For making connections to boilers, pumps, valves and other flanged outlets (and where piping must be frequently cleaned or inspected for corrosion), Midwest Lap-Joint Stub Ends have a tremendous advantage over flanges that are welded to the pipe (see drawings at right above). The swivel flange on the Stub End makes it unnecessary to accurately line up the bolt holes before welding; "setting up" is simple and quick because no special clamps or jigs are required to hold the face of the flange absolutely perpendicular to the axis of the pipe. The result is a real saving in time and cost of welding.

Another important economy is in erection. Field organizations report a saving of 25% in erection time for making up a joint using Midwest Lap-Joint Stub Ends in comparison with flanges rigidly fixed to the pipe; this saving is even greater when the flanges are on bends.

See Bulletin WF-41 for complete data regarding Midwest Lap-Joint Stub Ends . . . and the many other Midwest Welding Fittings that simplify and save on welded piping.

MIDWEST PIPING & SUPPLY CO., Inc.

Main Office: 1450 South Second St., St. Louis 4, Mo.


Plants: St. Louis, Passaic (N. J.) and Los Angeles

Sales Offices: Chicago—645 Marquette Bldg. • Houston—229 Shell Bldg. • Los Angeles—520 Anderson St. • New York—(Eastern Division) 30 Church St. • Tulsa—533 Mayo Building.





SCREWED AND
WELDED FLANGE

SLIP-ON FLANGE
WELDED FRONT
AND BACK




WELDING
NECK FLANGE



MIDWEST WELDING FITTINGS IMPROVE
DESIGN AND REDUCE PIPING COSTS



VULCAN ENGINEERED SOOT BLOWER INSTALLATIONS




Two 600,000 lb. per hour Combustion Engineering Co. Boilers installed in a large Eastern Central Station. Boilers generate steam at 1250 lb. per sq. in. at 910° F. Soot Blowers operate from 265 psi. Elements in the first pass are HyVULoy with HyVULoy protective bearings, air cooling and pre-cooling, resulting in long life in the exposed positions. This advantageous location together with slow-speed LG-2 heads keep the superheater clean. Also the use of the over-arm support and special sliding seal for large relative movements eliminate element warpage and give easy operation.

The NEW VULCAN CATALOG fully describing the MODERN VULCAN SOOT BLOWING SYSTEM is now available. Write for your copy.

VULCAN SOOT BLOWER CORPORATION, DU BOIS, PENNA.

At TOLEDO EDISON Company It's YARWAY All the Way

- YARWAY UNIT TANDEM Blow-Off Valves
- YARWAY HI-LO ALARM Water Columns
- YARWAY SESURE Inclined Water Gages



One of the Yarway HI-LO Alarm Water Columns and SESURE Inclined Water Gages in use at the Water Street Station of the Toledo Edison Co. This station, temporarily operating on 200 lb pressure, selected Yarway water level indicating equipment for that pressure range—will replace with higher pressure equipment when plant is stepped up to design pressure of 800 psi.

Many years of favorable experience with Yarway Blow-Off Valves led Toledo Edison to select them for their first high pressure unit—Acme Station—back in 1937. Six sets of Seatless and Hard-Seat Tandems were used, followed again in 1940 by 12 sets of Yarway Unit Tandems, making this station 100% Yarway Blow-Off Valve equipped.

More recently, when the 800 lb Integral Furnace Boilers were purchased for the Water Street Station (illustrated), four more Yarway Unit Tandems were installed.

The reason why high pressure utility and industrial power plants, one after another, select Yarway Blow-Off Valves is to be found in such records of performance as—"still tight after 3000 blows at more than 1300 psi, without the replacement of a single part or repairs of any nature."


Yarway Valves "stand up and take" the most severe demands made upon them because they are the result of over a quarter century of mechanical and metallurgical research and field experience.

Get this insurance against blow-off valve trouble and expense and resultant costly power shut-downs.

Write for Catalog, Section B-431 for pressures from 400 lb to 2500 lb. Section B-424 for lower pressures.


YARNALL-WARING COMPANY

101 Mermaid Ave., Philadelphia 18, Pa.



Yarway Unit Tandems are built for pressures up to 2500 lb. Combining a Hard-Seat and a Seatless Valve in a single, one-piece, forged steel body, this Tandem provides the advantages of both designs—for blowing or draining and sealing—in a single, compact, rugged unit.

The four Yarway Unit Tandem Blow-Off Valves on the 800 lb Integral Furnace Boilers at Toledo Edison's Water Street Station.



YARWAY

BLOW-OFF VALVES



OFFER 5 OUTSTANDING ADVANTAGES

● **A WEIGH LARRY COSTS LESS:**—than fixed chutes each fitted with necessary cut-off gates, scales, etc., when four or more boilers are to be served from a suspension bunker.

WEIGH LARRIES WEIGH THE COAL:—and permit an accurate card record to be kept of the coal consumption and operating efficiency of each boiler.

WEIGH LARRIES ELIMINATE SEGREGATION:—and produce an even dispersion of lumps and fines in the stoker hopper, resulting in ideal draft and burning conditions.

SIMPLIFIED BUILDING:—Weigh larries permit the use—if desired—of a cylindrical bunker located at the end of the building,—eliminating the

massive and costly structural supports needed for suspension bunkers, and the necessity of placing machinery, controls, etc., in front of the boilers,—thus assuring easy access to the boilers for repairs,—and ample light and ventilation.

PROVEN CONSTRUCTION:—Hand propelled and motor-driven,—floor and cage-operated types, having capacities from $\frac{1}{2}$ ton to 2 tons per load are standard. Special types to meet any requirements. All reflect the advantage of Bartlett-Snow's exacting design, and skillful painstaking manufacture.

Bulletin No. 83 gives full details and contains much information of interest to engineers and operating men. Send for a copy.

THE C. O. BARTLETT & SNOW CO.

6208 HARVARD AVENUE • CLEVELAND 5, OHIO

Engineering and Sales Representatives in Principal Cities

COAL HANDLING FOR CENTRAL STATIONS AND INDUSTRIAL BOILER PLANTS

TRACK HOPPERS • SKIP HOISTS • BUCKET ELEVATORS • BELT CONVEYORS
BINS AND BUNKERS • WEIGH LARRIES • FIELD STORAGE • ASH HANDLING


Solutions

TO YOUR TOUGH INSULATING PROBLEMS!

WHATEVER your insulating problem, there's a Johns-Manville insulation that can solve it efficiently and at minimum cost. For, over the past 86 years, J-M's extensive laboratories have pioneered in the field of industrial insulation. Today J-M offers a wide line of insulating materials, each designed for some specific insulation need, for temperatures up to 2600°. For example:



For temperatures to 600° F. J-M 85% Magnesia has been for many years the most widely used block and pipe insulation for temperatures to 600° F. and, in combination with Superex, for higher temperatures. Maintains high insulating efficiency. Standard block sizes 3" x 18", 6" x 36" and 12" x 36"; from 1" to 4" thick.




Furnace insulation up to 2600° F. J-M Insulating Brick and Insulating Fire Brick are available in 7 types, temperature limits from 1600° F. to 2600° F. All provide light weight, low conductivity. New Insulating Fireblok, now ready in all four Fire Brick types, are 5 times larger for speedier, more economical installation.



For steam lines up to 700° F. Use J-M Asbesto-Sponge Felted Pipe Insulation for efficiency, high salvage and resistance to abuse. For temperatures over 700° F. use with Superex. In 3-ft. lengths 1" to 3" thick.



Insulation for temperatures to 1900° F. J-M Superex Blocks have long been standard for this service. High heat resistance, low thermal conductivity. Sizes 3" x 18", 6" x 36" and 12" x 36"; from 1" to 4" thick.



For more details on these materials, and on the complete J-M Insulation line, write for Catalog GI-6A. Address: Johns-Manville, 22 East 40th Street, New York 16, New York.



Johns-Manville INDUSTRIAL INSULATIONS

FOR EVERY TEMPERATURE... FOR EVERY SERVICE



ADD ***ALL 3*** TO YOUR MODERNIZATION PLANS
THROUGH

PREHEAT *Engineering*

If you are planning to modernize a boiler plant, oil refinery heater or other industrial furnace, don't overlook the possibilities for more effective use of preheated air.

IMPROVED COMBUSTION. A shorter, hotter flame helps complete combustion before gases leave the furnace. Higher rates of liberation increase furnace capacity. High-moisture powdered coal and low grade fuel such as screenings, coke breeze, etc., may be effectively burned.


BETTER HEAT RECOVERY. Flue gas temperatures may be reduced 200 to 500 degrees, and the heat returned with minimum loss to the incoming combustion air. Thermal efficiency of the furnace may be increased up to 10% or more.

SAVINGS IN PLANT MATERIALS. The Ljungstrom Preheater is unusually compact, effecting savings in weight of both heating surface and supporting structure. In many cases, the Ljungstrom weighs less than half as much as other heat recovery installations with the same capacity.

ENGINEERING SERVICE. The engineering staff of the Air Preheater Corporation is prepared to assist you in applying either the standard or special types of Ljungstrom Preheaters to your present plant, or to assist you in engineering it as an integral part of new units.

THE LJUNGSTROM AIR PREHEATER.

Either vertical or horizontal types consist of a cellular rotor which "soaks up" heat from flue gas as it passes through, and transfers it to the cold, incoming air. It works on the continuous regenerative flow principle, thus giving maximum heat transfer with minimum weight and size.



THE AIR PREHEATER CORPORATION

Executive Offices: 60 East 42nd Street • New York 17, N. Y. • Plant: Wellesville, N. Y.

COTTRELL PROCESS

of

ELECTRICAL PRECIPITATION

universally recognized as a
standard method of removing

DUST, FLY ASH, FUME, MIST & FOG
from GASES

•

30 years of research, development and operating experience
throughout the world are incorporated in the
COTTRELL INSTALLATIONS

offered to meet the requirements
of any problem by

RESEARCH CORPORATION

405 LEXINGTON AVENUE
NEW YORK CITY 17

59 EAST VAN BUREN STREET
CHICAGO, ILL.

Boiler room essentials by ELLIOTT



Elliott has kept pace with his tory in the progress of steam generation. In fact has actually set the pace in some developments, notably that of deaeration. So it is not surprising that the Elliott monogram is a familiar mark on much boiler room equipment of both primary and secondary importance. This equipment is in full tone shown on this page.

Though less easy to portray pictorially, the confidence of experienced engineers in the use of this Elliott equipment is an equally vital factor in the profitable operation of a great many boiler rooms.

Q-1110

ELLIOTT Company

DISTRICT OFFICES IN PRINCIPAL CITIES

JEANNETTE, PA. • RIDGWAY, PA. • SPRINGFIELD, OHIO

HALL P-T-X SYSTEM

• the added factor in a

Hall research has scored another first in its development of the

P-T-X System to control deposition in boilers and turbines

and to prevent corrosion from bonded oxygen

WHEN medical science perfects a remedy for a baffling disease, your physician is that much better fortified to keep you in good health.

The same holds true in the treatment of boiler ills. The new Hall P-T-X System for coping with certain boiler conditions which have heretofore resisted every attempt at a solution, makes Hall Service of preventive care more than ever a modern necessity.

To prospective users of Hall Boiler Service this gives an added promise of freedom from troubles arising from boiler water conditions. To the hundreds of leading plants which have consistently used this service, it is new evidence of the security it affords.

Preventive care, practiced by the Hall Labo-

ratories trained field personnel, owes its successful performance to one factor which should mean more to you than any other—Hall Laboratories' unceasing research.

Every boiler ill reveals itself through symptoms to the trained observer. Preventive care is a system which enables you to detect these symptoms and apply a remedy before it is too late. This individualized operation explains the overwhelming success of Hall Serviced power plants. May we give you further particulars?

Siliceous scales can now be reduced or eliminated (see photo) in high and low pressure boilers by the new Hall P-T-X system based on a potassium equilibrium instead of sodium. This is a new treatment added to Hall Service to meet certain conditions. It does not replace or make obsolete the present Hall System. ➡

HALL LABORATORIES, INC. • HAGAN BUILDING • PITTSBURGH 30, PA.

A SUBSIDIARY OF
HAGAN CORPORATION



HALL SYSTEM

famous boiler service


Unique Advantages of the new P-T-X System

as developed by Hall Laboratories

- 1 Siliceous scales can be reduced or eliminated in the boiler proper because, in the concentrating-film boiler water, potassium silicates have high solubilities increasing markedly with temperature, as compared with sodium silicates, whose solubilities are lower and decrease with temperature.
- 2 Corrosion and embrittlement. The highly-soluble potassium salts have the advantage in setting up conditions for reducing corrosion from bonded oxygen and minimizing any tendency toward embrittlement.
- 3 Deposition in superheaters can be controlled more effectively by maintaining equilibria designed to keep any unavoidable carryover in harmless form.
- 4 Hide-out can be reduced and practically eliminated because the potassium salts concerned are more soluble than the corresponding sodium salts. (See 1.)
- 5 Turbine conditions can be improved by recognizing the special factor of decomposition of silicates with decreasing temperature and taking measures to oppose this with suitable alkalinity.
- 6 Toleration of silica permits adequate control of magnesium ion by insuring the presence of enough silica to result in removal as non-adherent magnesium silicate.
- 7 Circulation is improved because siliceous scale formation, accumulation of iron-oxide and deposition from hide-out are reduced.
- 8 Higher boiler ratings are possible without difficulty from deposition or attack of steel.
- 9 Elaborate and costly silica removal equipment should be unnecessary except in unusual cases.

of Boiler Water Conditioning

The Army's Answer to a **"MUST!"**



"Thunderbolt"—said to be the most powerful single seat fighter in the world, with four .50 caliber fixed machine guns mounted in each wing panel, a flying speed of more than 400 m. p. h.—and a diving speed greater than the speed of sound.

"Musts" are constant in industrial, as in military achievements. And the only "stock-bin" out of which "musts" are solved is the stock-bin of experience and specialized application. POWELL, for nearly one hundred years, has made valves, and valves only . . . valves for all flow control requirements . . . valves for the "must" requirements in all fields of industry . . . in war or peace . . . through ten decades of industrial progress. Our experience in producing *the* valve to do *the* specific job—"to meet the must"—is yours on request.



The Wm. Powell Co.

Dependable Valves Since 1846

Cincinnati 22, Ohio



Fig. 150 (above)—Bronze "Union Disc" Globe Valve for 150 pounds W. P. Has screwed ends, union bonnet, and renewable vulcanized composition disc—especially suitable for throttling service—for controlling low-pressure steam, oil, water, gas, etc.

Fig. 375 (below)—Bronze Gate Valve for 200 pounds W.P. Has screwed ends, union bonnet, inside screw rising stem and a special hard bronze disc.

Fig. 1708 (above)—Bronze Globe Valve for 200 pounds W.P. Has screwed ends, union bonnet, renewable seat and regrindable, renewable hard bronze semi-cone plug type disc—especially suitable for throttling service—for controlling low-pressure steam, oil, water, gas, etc.

POWELL VALVES

DOWELL INDUSTRIAL CHEMICAL CLEANING SERVICE

Increasing Industry's Productive Power

A quick—safe—efficient method of chemically removing water- or steam-deposited scales and sludge from all types of heat exchange equipment is provided by Dowell to help restore and increase industry's productive efficiency.

This proven chemical service is completely mobile

and readily available at many strategic points.

The close cooperation between Dowell and its parent organization, The Dow Chemical Company, is fully utilized to provide industry with advanced methods and improved techniques in chemical cleaning.

Consult the nearest Dowell office for full information.




DOWELL INCORPORATED

529 Kennedy Building
Tulsa 3, Oklahoma

New York • Philadelphia • Cleveland • Chicago • St. Louis
Kansas City • Long Beach • Salem, Ill. • Mt. Pleasant, Mich.
Houston • Wichita, Kan. • Casper, Wyo.





DANGEROUS WATERS

● The best defense is a well organized offense . . . whether waging a war in dangerous waters or fighting water problems in industrial production.

Water . . . unconditioned . . . when carried to vital spots in your plant, can waste fuel, increase labor costs, ruin vital equipment and wreck production schedules.

Today, effective water conditioning is a "must" in the battle against scale, corrosion, embrittlement, oil, etc.

You are invited to call on Infilco's Engineering staff to help in any problem of boiler or evaporator feedwater treatment, cooling water conditioning, condensate oil removal, steam purification, trade waste treatment, etc.

INFILCO
INCORPORATED

325 W. 25TH PLACE, CHICAGO, ILL.



ACCELATOR SOFTENERS • CHEMICAL FEEDERS • PROPORTIONERS
WATER FILTERS • CLARIFIERS • COOLING WATER CONDITIONERS
CONDENSATE FILTERS • STEAM PURIFIERS • HOT-FLOW SOFTENERS
LIME-SODA SOFTENERS • ZEOLITE SOFTENERS • CATEXERS





the most **AMAZING** Castable Refractory in Engineering History!

NEW! Nothing Like Kast-O-Lite
INSULATION FOR USE TO 2500° F.
IN DIRECT CONTACT WITH FLAME

There is no other castable like Kast-O-Lite. It's INSULATION plus CASTABLE for use in direct contact with flame to 2500°F. **DON'T CONFUSE THIS NEW ACHIEVEMENT IN INSULATING CASTABLES WITH GENERALLY OBTAINED CAST-REFRATORIES FOR USE TO ONLY 1800° TO 2200°F.** Kast-O-Lite has a fireclay base—a high P. C. E.—and like no other insulating castable, will withstand continued direct exposure to furnace gases to 2500°F.

KAST-O-LITE combines insulating properties and light weight with strength in one dependable, easy-to-use, castable refractory.

Now, for dozens of industrial and boiler furnace uses, you can have all the advantages of an efficient, reliable castable refractory—plus the economy and heat saving benefits of insulating firebrick.

All of these properties are combined in KAST-O-LITE, the most amazing refractory material in engineering history. Used in actual service in every type of installation where an insulating castable is desirable and imposing every possible test—KAST-O-LITE has exceeded every operating requirement.



Wide Range of Uses

Because KAST-O-LITE is not only a castable—or just an insulation—but a dependable combination of both—it offers a wide range of uses. Wherever insulating refractory properties are desired, KAST-O-LITE offers construction advantages and economy. For complete linings, walls, arches or special shapes.

Easy to Use

KAST-O-LITE, as its name implies, may be cast into place using simple formwork in much the same manner as structural concrete. Mix with water and puddle or pour. Furnace walls, arches, linings or back-up are placed in monolithic sections. Shapes can be made easily and quickly.



Quick Delivery— Local Stocks & Service

Warehouse stocks of KAST-O-LITE are located near you for prompt delivery. Look in the classified section of your local telephone directory for the name of your nearest A. P. Green representative. He'll be glad to show you more about the advantages of KAST-O-LITE.



U. S. MARITIME "M" FOR PRODUCTION ACHIEVEMENT

A. P. GREEN
FIREBRICK COMPANY





the First Name in Refractories

MEXICO, MISSOURI

Cuts Fuel Bills!

SAVES—REDUCES HEAT LOSSES



The light weight and composition of KAST-O-LITE means that less heat is lost through the lining. Thermal conductivity as used is only approximately 30% that of heavy firebrick. This denotes only 6" of KAST-O-LITE is equal to 18" of firebrick in insulating value. Closer temperature control is possible. Fuel savings result.

And because KAST-O-LITE weighs only 78 lbs. per cubic foot the weight of the lining can be reduced approximately 50% as compared with heavy firebrick.

KAST-O-LITE
INSULATING CASTABLE
REFRACTORY



15 HENDY FEATURES

In the turbine—

1. Economical water rate per kw-h.
2. Rigid spindles with discs having large hub sections form the backbone of the turbine structure and assure greater strength.
3. Step cut labyrinth diaphragm seals.
4. Steel Rateau nozzle discs with welded-in, rolled stainless steel nozzle blades and spacers.
5. Governing system that uses anti-friction bearings and is without stuffing boxes or soft packing.
6. Smooth, compact design without sacrifice of accessibility.

In the reduction gear—

7. Fabricated steel gear case, smoothly finished—no sharp corners or edges.
8. Rigidity combined with light weight.
9. External piping reduced to a minimum.

In the generator—

10. Rolled steel-plate field yoke of split type with halves bolted together.
11. Shock-proof, solid construction, giving greatest safety under adverse conditions.
12. Liberally dimensioned, providing capacity for emergency overloads.
13. High efficiency through careful design.
14. Self-aligning sleeve type bearing mounted in spherical seat insuring simple alignment of shaft.
15. Sixty-six years of generator building experience.

EST. 1856



BRANCH OFFICES



New..
POWER

*for a more
electrified America*

Built to the rigid requirements of U.S. Navy and Maritime Commission specifications for war service today, this Hendy Turbo-generator plant forecasts the standards for postwar electric generating equipment.

In developing its rugged, compact design, Hendy engineers swept the boards of old ideas—the result is a unit of sound reliability and long service life.

Construction features normally found only in larger turbo-generators are in these new Hendy power plants. These features insure larger factors of strength and safety, more economical operation and higher over-all efficiency.

Hendy turbo-generating plants are designed in a range of 250 to 750 kw permitting their use in a wide variety of marine and industrial service. Submission of your specification requirements is invited.

JOSHUA HENDY Division
JOSHUA HENDY IRON WORKS

SUNNYVALE, CALIFORNIA

Boston • Buffalo • Chicago • Cincinnati • Cleveland • Detroit • New York • Philadelphia • Pittsburgh • San Francisco • St. Louis • Washington • Los Angeles



TURBO-GENERATORS



REDUCTION GEARS



STEAM TURBINES



DIESEL ENGINES

Investigate Fairmont Coal



NEVER AGAIN BE CAUGHT SHORT — with obsolete fuel-burning equipment which puts your plant in a "strait jacket."

Thousands of industrial plants are in distress today because they cannot burn a wide range of steam coals.

Start planning now to modernize your boiler plant as soon as priorities are lifted.



Many of the best coals in America are "low fusion" coals and earn "high profits" when burned in modern equipment with adequate design factors.

Fairmont Coal is a "top flight" coal in this category.

Learn the "Fairmont Story" and discuss it with manufacturers of combustion equipment.

COAL BUREAU — UPPER MONONGAHELA VALLEY ASSN.
Chanin Bldg. 122 E. 42nd St., New York 17, N. Y.

COAL BUREAU FUEL ENGINEERS ARE READY TO HELP YOU

You incur no obligation in drawing on the experience of the Bureau's staff of Fuel Engineers to help you in selecting the equipment best adapted to your specific needs and in determining the proper course to pursue in evaluating fuel from a long-range standpoint. Ask for this assistance freely.

COMBUSTION—June 1944

COAL BUREAU — UPPER MONONGAHELA VALLEY ASSN.
Chanin Bldg., 122 E. 42nd St., New York 17, N. Y.

Kindly place me on your mailing list to receive copies of "Reference Bulletins." It is understood these will be sent me FREE and without obligation.

Name.....
Company.....
Position.....
Address.....

Progress and Power in the **TEXTILE**

Perhaps no other industry is quite as dependent on low cost, dependable electrical energy as textile and rayon manufacturers. America's great Public Utilities have met all the requirements of this ever expanding group in widely scattered sections all over the United States.

American Blower engineers, too, have contributed much to the task of making rayons and cloth of all types at low cost. For many years American Blower fans, blowers, air conditioning units and humidifiers have been maintaining healthful, efficient working conditions in the plants of the textile and rayon industries.

Furnishing vital equipment of standard as well as specialized types for handling of air in industry, and building mechanical draft equipment, dust collectors and fluid drives, is our job. May we co-operate with you?




AMERICAN BLOWER



AMERICAN BLOWER CORPORATION, DETROIT, MICH.
CANADIAN SIROCCO COMPANY, LTD., WINDSOR, ONT.

Division of AMERICAN RADIATOR & Standard Sanitary CORPORATION




American Blower Fan for exhausting organic fumes from spring room machines in a rayon plant.

Rotors for American Blower Air Supply Fans used in connection with central air conditioning systems in textile plants.



LAND RAYON INDUSTRIES



(Above) American Blower Central System Air Conditioner and Washer for a rayon plant.



(At Right) Air Conditioning and Humidifying unit built by American Blower for one of America's largest textile mills.

THESE TUBES HAVE BEEN PROVED

by more than

120,000,000

Republic ELECTRUNITE Boiler, Condenser and Heat Exchanger Tubes are not new products. Long ago they proved *CONCLUSIVELY* their safety, soundness, ease of installation and economy in service.

The first ELECTRUNITE Pressure Tubes were installed in 1932—and immediately began to establish records. Today, more than 120,000,000 feet have been installed in all types of steam generating and heat transfer equipment, in every kind of service.

Because of the advantages *CONSISTENTLY* afforded by the ELECTRUNITE process of manufacture, these tubes are unusually easy to install. They slide in readily—roll to tight joints freely and quickly—cut installation costs.

Their smooth, scale-free surface retards corro-

sion. Their uniform strength and the rigid tests made after every step in the ELECTRUNITE process assure positive safety in *EVERY* tube.

Companion products made by the same process—some 30,000 miles of Republic Line Pipe, 50,000,000 feet of oil well casing and tubing, and more than 1,000,000,000 feet of aircraft and mechanical tubing in carbon, alloy and stainless steels—also have added indisputable proof of the soundness, safety and economy of Republic Electric Weld Tubular Products.

Would you like to know more about ELECTRUNITE Tubes, how they are tested, where and how long they have been installed? Write us.

REPUBLIC STEEL CORPORATION STEEL AND TUBES DIVISION • CLEVELAND 8, OHIO

Berger Manufacturing Division
Culvert Division • Niles Steel Products Division
Union Drawn Steel Division • Truscon Steel Company
Export Department: Chrysler Building, New York 17, New York




BUY MORE THAN BEFORE
IN THE FIFTH WAR LOAN



Feet in Service



TERRY



THE ROTOR OF THIS BOILER FEED TURBINE IS DOUBLE RIM PROTECTED!

The 1250 H. P. Turbine shown above employs the Terry Solid Wheel Rotor. The wheel is made from a single steel forging and the buckets are milled directly in the wheel.

The buckets are protected by rims at the sides of the wheel. These rims would take without damage any rubbing that might occur if the clearance became reduced.


With this construction it is impossible for the blades to foul and frequent inspections of the thrust bearing are not required to obtain safe and dependable operation.

The Terry Wheel Turbine is fully described in our Bulletin S-116.

T-1152

**THE TERRY STEAM
TURBINE COMPANY**
TERRY SQUARE, HARTFORD, CONN.

How a film .0025" thick *adds years of life* TO BOILERS



APEXIOR...a technical protective coating for mechanical equipment

An impenetrable barrier against water, which will add years of life to new boilers and provide added service from old boilers... is available to you in APEXIOR NUMBER 1. Two coats of this high temperature water and steam resistant paint, measuring .0025" in thickness, will resist wear and corrosion over a long period of time. And it is renewable by applying a single coat when needed, possibly once in two to three years.

Under average conditions, and when boiler deposits, if any, can be washed down or removed by means of a light bristle or wire brush, the coating may last for several years. A single make-up maintenance coat is generally necessary after mechanical cleaning with a sharp cutting head.

APEXIOR is brush-applied by hand or power-coater. It is easily renewed.

Painting boiler metal with APEXIOR is recommended by boiler insurance companies. And many manufacturers of turbines coat shafts, rotor bodies, and frequently interiors of casings with APEXIOR before shipping to customers.

Hundreds of operators have used APEXIOR NUMBER 1 for years as an economical means of boiler maintenance. Recently, many more have adopted APEXIOR as a guarantee of longer life for metal that cannot be replaced. They discovered that boilers nearing the end of their life, if able to pass inspection and a hydrostatic test, could be APEXIORIZED for years of extra service.

HOW TO GET PEAK PRODUCTION WITH PEAK PROTECTION

Write today for bulletin 1290 (*Industrial*) or 1305 (*Marine*) describing APEXIOR in detail. APEXIOR is used by such representative organizations as these:

The Detroit Edison Co.
Gulf Shipbuilding Corp.
Curtiss-Wright Corp.
Louisville Gas & Electric Co.
American Smelting & Refining Co.
National Biscuit Co.
Union Carbide & Carbon Corp.
Socony Vacuum Oil Co.
Carnation Co.
Illinois Central R. R. System



A Peacetime Plus ★ ★ ★ A Wartime Must

RECOMMENDED BY ALL U. S. AND CANADIAN BOILER INSURANCE COMPANIES

The **DAMPNEY COMPANY**
of America
protective coatings for

STATIONARY BOILERS, LOCOMOTIVES AND STEAMSHIPS

THE DAMPNEY COMPANY OF AMERICA
Hyde Park 36, Mass.

Please send free Bulletin 1290 (*Industrial*) ☐
1305 (*Marine*) ☐

Name.....

Company.....


Address.....

Main Office: HYDE PARK • BOSTON 36, MASS. • Branch Offices: ATLANTA • CHICAGO • NEW YORK • DETROIT • PHILADELPHIA
Engineering Sales Representatives — Pittsburgh, Cincinnati, New Orleans, San Francisco, Los Angeles, Portland, Seattle, Phoenix, Denver,
Salt Lake City, Dallas, Houston, Vancouver, B. C., Montreal, P. Q., Havana, Cuba, Honolulu, T. H.,
Marine Dept., 114 Liberty Street, New York City, N. Y.

He won't dodge this-



Don't you dodge this!



The kid'll be right there when his C. O. finally gives the signal . . .

There'll be no time to think of better things to do with his life. THE KID'S IN IT FOR KEEPS—giving all he's got, *now!*

We've got to do the same. This is the time for us to throw in everything we've got.

This is the time to dig out that extra hundred bucks and spend it for Invasion Bonds.

Or make it \$200. Or \$1000. Or \$1,000,000 if you can. There's no ceiling on this one!

The 5th War Loan is the biggest, the most vitally important financial effort of this whole War!



***Back the Attack!* - BUY MORE THAN BEFORE**

COMBUSTION PUBLISHING COMPANY, INC.

★ * This is an official U. S. Treasury advertisement—prepared under the auspices of Treasury Department and War Advertising Council

★

Let's Check the Record



CROSBY PRESSURE RECORDERS are used in power stations, process plants, refineries, textile mills—wherever a permanent record of pressure is desired—wherever accuracy, sensitivity and dependable operation are demanded.

Furnished in 10" and 12" chart sizes, for recording up to four pressures on same chart.




CROSBY



STEAM GAGE AND VALVE CO.

BOSTON • NEW YORK • CHICAGO
LOS ANGELES • DALLAS

Next to Split-Duct Manifolds . . . INNER WELDS GROUND SMOOTH



No. 6 Reason for

Buell's High Efficiency, Low Maintenance, Long Life


• THE PROPER FINISHING of the inner surface of all welds in Buell (van Tongeren) Cyclones has a direct bearing upon first, their operating efficiency, second, their length of life.

Any projection in a gas stream will affect the efficiency of a dust collector. Surface irregularities create undue turbulence and cause the reentrainment in the gas stream of previously separated dust particles. Moreover, if the weld-bead is not ground smooth, rapid erosion of the surface beyond the bead will take place, due to the formation of a local eddy current at this point. And continued erosion will shorten the life of the stoutest dust collector.

Smoothly ground inner welds are one more reason for Buell's high efficiency, long life, trouble-free operation, and low maintenance cost. Reasons supported by the wide use of Buell Dust Recovery Systems throughout industry.

Write for a copy of the illustrated book—"The van Tongeren System of Industrial Dust Recovery," containing facts about this patented system, interesting alike to engineer and executive.

BUELL ENGINEERING COMPANY, INC.
Suite 5000, 70 Pine St., New York 5, N. Y.
Sales Representatives in Principal Cities



buell
DUST RECOVERY
SYSTEMS

BUELL FEATURES	RESULT IN	PRODUCE
SHAVE-OFF	HIGH COLLECTION	GREATER RECOVERY
LARGE DIAMETERS	EFFICIENCY	LOW MAINTENANCE
EXTRA-THICK METAL	LESS FAN BLADE WEAR	LOW OPERATING
LARGE OUTLETS	LOW DRAFT LOSS	COST
INNER WELDS	LOW POWER	LONG LIFE
GROUND SMOOTH	CONSUMPTION	NO CLOGGING
CORRECTLY DESIGNED	HIGH TEMPERATURE	
HOPPERS	RESISTANCE	
SPLIT-DUCT	UNLIMITED CAPACITY	
MANIFOLDS	NO MOVING PARTS	
	FREE DUST FLOW	


DESIGNED TO DO A JOB, NOT JUST TO MEET A "SPEC"

Where Soot Blowers Have to be Good

The Choice is Almost Invariably
DIAMOND

Diamond Soot Blowers are almost a foregone conclusion in huge central station and industrial steam power plants. An overwhelming majority of engineers choose them because they know Diamond Blowers will stand the extreme severity of service—keep boilers cleaned of soot and slag and require little attention from the service man.

More than 80% of all the soot blowers on modern power boilers are Diamond.



DIAMOND POWER SPECIALTY CORPORATION • Detroit, Michigan
DIAMOND SPECIALTY LIMITED • WINDSOR, ONTARIO


COMBUSTION

LOSING B.T.U.s?



SIMPLY APPLY UNIBESTOS
it's simple to apply!

Consider these important heat-saving factors in UNIBESTOS construction and method of application: It is available in half-section form up to 30" pipe diameter and in quarter sections from 32" to 60", in thicknesses from $\frac{3}{4}$ " to 5" . . . affords a neat, tight job without efficiency-impairing gaps. Standard UNIBESTOS is available for service up to 750°; combinations of Standard and Super UNIBESTOS in single layer construction are available for service up to 1200°. These temperature limits permit the use of one material at maximum efficiency for a wide range of purposes.



UNION ASBESTOS
MEANS PROGRESS IN INSULATION
AND RUBBER CO.



COPYRIGHT 1944
UNION ASBESTOS & RUBBER CO.

FACTORY AND GENERAL OFFICES: 1821 S. 54th Ave., CICERO, ILL.
NEW YORK • SAN FRANCISCO • PATERSON, N. J.

